

TS: 1 110043  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-129-20,817-0600  
W/2 W/2 SW, SEC. 23, T 31 S, R 40 W/E  
1320 feet from S section line  
4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5181

Lease Name Davis Well # 1-23  
County Morton 195.00

Operator: Donald C. Slawson  
Name &  
Address Suite 700, 20 N. Broadway  
Oklahoma City, OK 73102

Well Total Depth 6000' Upper Morrow feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 1573

Abandoned Oil Well  Gas Well  Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ O&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Slawson Drilling Co., Inc. License Number 5657

Address P.O. Box 1409, Great Bend, KS 67530

Company to plug at: Hour: 11:45 pm Day: 21 Month: July Year: 1986

Plugging proposal received from Jack Richardson

(company name) Slawson (phone) (316) 793-3561

were: to fill hole with heavy mud and spot cement through drill pipe Elevation 3298'  
Anhydrite N/A/E/D

- 1st plug at 2800' with 50 sx cement
- 2nd plug at 2450' with 50 sx cement
- 3rd plug at 1620' with 50 sx cement
- 4th plug at 700' with 40 sx cement
- 5th plug from 40' to surface with 10 sx cement
- 6th plug to circulate rat hole with 10 sx cement
- 7th plug to circulate mouse hole with 10 sx cement

STATE CORPORATION COMMISSION  
CONS. DIV. WICHITA, KS

7-29-86

JUL 29 1986

Plugging Proposal Received by Jack R. Kapp  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 3:30 am Day: 22 Month: July Year: 1986

ACTUAL PLUGGING REPORT 1st plug spotted at 2800' with 50 sx cement, 2nd plug spotted  
at 2450' with 50 sx cement, 3rd plug spotted at 1620' with 50 sx cement, 4th  
plug spotted at 700' with 40 sx cement, 5th plug spotted from 40' to surface  
with 10 sx cement, 6th plug to circulate rat hole with 10 sx cement, 7th plug  
to circulate mouse hole with 10 sx cement.

Remarks: Used 60/40 Poz with 6% gel by Halliburton. Used 600 sx drispac mud: viscosity 54  
weight 9.2  
(If additional description is necessary, use BACK of this form.)

**INVOICED**

DATE JUL 29 1986

INV. NO. 14543

7-22 AUG 29 1986

Signed James R. Kapp  
(TECHNICIAN)