

1 060567

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 129-20,756-~~8800~~

NW SE SE, SEC. 2, T 31 S, R 41 W/X

1250 feet from S section line

1250 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 7041

Lease Name Jean Donaghy Well # 1-2

Operator: Charles B. Wilson, Jr.

County Morton

Name & Address 1616 W. Loop South, Suite 310

(Hugoton)  
Well Total Depth 2350 76.38 feet

Houston, TX 77027

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 640

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Service Drilling Co. License Number 5987

Address Box 5320, Borger, TX 79007

Company to plug at: Hour: 8:00 pm Day: 10 Month: May Year: 19 85

Plugging proposal received from Sam Staats

(company name) Service (phone) 806-273-7535

were: to fill hole with heavy mud and spot cement through drill pipe Elevation 3370  
Anhydrite 1300-1320

1st plug at 1320' with 50 sx cement

2nd plug at 660' with 50 sx cement  
solid bridge

3rd plug hulls - plug at 40' -- cement to surface with 10 sx cement

5th plug to circulate rat hole with 15 sx cement

Plugging Proposal Received by Paul A. Luthi

(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None

Operations Completed: Hour: 9:30 pm Day: 10 Month: May Year: 19 85

ACTUAL PLUGGING REPORT 1st plug at 1320' with 50 sx cement, 2nd plug at 660' with 50  
sx cement, 3rd & 4th plugs - solid bridge - hulls - plug at 40' -- cement to surface  
with 10 sx cement, 5th plug to circulate rat hole with 15 sx cement.

RECEIVED  
STATE CORPORATION COMMISSION

MAY 21 1985 S-21-85

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Dowell  
(If additional description is necessary, use BACK of Wichita, Kansas)

CONSERVATION DIVISION

IN WICHITA (did not) observe this plugging.

Signed Paul A. Luthi  
(TECHNICIAN)

DATE 5-21-85

INV. NO. 8229 S-10