

To: 1 020433
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

1-31 API NUMBER 15- 175-21,163-0000 161 P
E/2 E/2 NE SEC. 21, T. 31 S, R. 33 W/8

TECHNICIAN'S PLUGGING REPORT

Operator License # 5363
Operator: BEREXCO Inc.
Name & Address: P.O. Box 723
Hays, KS 67601

3960 feet from S section line
330 feet from E section line
Lease Name Howard Well # 1
County Seward 191.75
Well Total Depth 5900 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 1610

Abandoned Oil Well Gas Well Input Well _____ SWD Well _____ D&A _____
Other well as hereinafter indicated _____

Plugging Contractor Sargent's Casing Pulling License Number 6547
Address P.O. Box 506, Liberal, KS 67901

Company to plug at: Hour: 10 a.m. Day: 29 Month: 1 Year: 19 92

Plugging proposal received from Kirby Lillard
(company name) Sargent's Casing Pulling (phone) 316-624-7455

were: 4 1/2" at 5903.7' w/250 sx cement, DV at 300' w/300 sx cement, PBTD 5856'
TOC @ 2000', Perfs at 5471-80, 4849-52'

1st plug pump 1 sx hulls and 30 sx cement,
2nd plug at 1640' with 50 sx cement. 3rd plug at 800' with 40 sx cement,
4th plug at 40' with 10 sx cement.

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part None _____
Operations Completed: Hour: 11:30 a.m. Day: 31 Month: 1 Year: 19 92

ACTUAL PLUGGING REPORT 1st plug pumped 1 sx hulls and 15 sx cement, 1 sx hulls and 15 sx cement displaced with mud,
loaded hole with mud,
2nd plug pumped 50 sx cement at 1640',
3rd plug pumped 40 sx cement at 700',
4th plug pumped 10 sx cement at 40'. to -4'.
All plugs displaced with mud.

STATE CORPORATION COMMISSION
FEB 04 1992
CONSERVATION DIVISION
WICHITA, KANSAS

Remarks: Used common cement by Sargent's. Recovered 2204' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOLVED

(If applicable) observe this plugging.

DATE 2-12-92
INV. NO. 34513

Signed Glen R. Barlow (TECHNICIAN)