

1 080051

2-20

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
290 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 175-21,129-0050
C NW SW, SEC. 26, T 31 S, R 33 (W/E)
1980 feet from S section line
4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9953
Operator: Harris Oil & Gas
Name & Address: 1775 Sherman Street, Suite 2990
Denver, CO 80203

Lease Name Becker Well # 1-26
County Seward 195.00
Well Total Depth 6000 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 1535

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A
Other well as hereinafter indicated _____

Plugging Contractor BEREDCO Inc. License Number 5147
Address 401 East Douglas, Suite 402, Wichita, KS 67202

Company to plug at: Hour: 5 p.m. Day: 20 Month: 2 Year: 19 90

Plugging proposal received from Gary Marshall

(company name) BEREDCO Inc. (phone) 316-265-2856

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1875'
1st plug at 3050' with 100 sx cement, 2nd plug at 1880' with 50 sx cement,
3rd plug at 950' with 50 sx cement, 4th plug at 40-0' with 10 sx cement,
5th plug to circulate rathole with 15 sx cement,
6th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Mike Spain (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None

Operations Completed: Hour: 9 p.m. Day: 20 Month: 2 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug at 3050' with 100 sx cement,
2nd plug at 1880' with 50 sx cement,
3rd plug at 950' with 50 sx cement,
4th plug at 40-0' with 10 sx cement,
5th plug to circulate rathole with 15 sx cement,
6th plug to circulate mousehole with 10 sx cement.

Remarks: USED 60/40 Pozmix 6% gel by Halliburton.
STATE CORPORATION (if additional description is necessary, use BACK of this form.)

INVOICED

DATE 2-2-90
INV. NO. 2-20

Signed Mike Spain (TECHNICIAN)

FORM C - EFFECTIVE DATE: 2-9-90

State of Kansas 175-21,129-0000

NOTICE OF INTENTION TO DRILL

CDR MUST BE SIGNED ALL BLANKS MUST BE FILLED

Must be approved by the K.C.C. five (5) days prior to commencing well

Expected Spud Date .. February .. 10, 1990 .. month .. day .. year

C NW SW Sec 26 Twp 31 S, Rg 33 East West

OPERATOR: License # 9953 Name: Harris Oil & Gas Address: 1775 Sherman Street, Suite 2990 City/State/Zip: Denver, CO, 80203 Contact Person: Bud Harris Phone: (303) 831-1303

1980 feet from South line of Section 4620 feet from East line of Section (Note: Locate well on Section Plat Below)

CONTRACTOR: License #: 5147 Name: BEREDCO, INC.

County: Seward Lease Name: Becker Well #: 1-26 Field Name: (Angel North.) unknown Is this a Prorated Field? yes X no Target Formations: St. Louis Nearest lease or unit boundary: 660' Ground Surface Elevation: 2870' feet MSL Domestic well within 330 feet: yes X no Municipal well within one mile: yes X no Depth to bottom of fresh water: 480' Depth to bottom of usable water: 570' Surface Pipe by Alternate: X 1 2 Surface Pipe Planned to be set: 1500' Conductor pipe required: 0' Projected Total Depth: 6050' Formation at Total Depth: St. Louis Water Source for Drilling Operations: X well farm pond other OUR Permit #: applied for Will Cores Be Taken? yes X no If yes, proposed zone:

Well Drilled for: Well Class: Type Equipment: X all Inj X Infields X Mud Rotary X Gas Storage Pool Ext. Air Rotary OWD Disposal Wildcat Cable Seismic: # of Holes

If OWD: old well info as follows: Operator: Well Name: Comp. Date: Old Total Depth

Directional, Deviated or Horizontal wellbore? yes X no If yes, total depth location:

Exp. 8/2/90

Move LW Set 1535 of 2-10-90

AFFIDAVIT

600' Alt. I Req.

PUSHER Gray Marshall TD 6000 FORMATION St Louis (wet in the Army) SURFACE PIPE 1535 @ 8 5/8 ANHYDRITE 1875 ELEVATION STARTING TIME & DATE 5:00 PM - COMPLETION TIME & DATE 9:00 PM 2-20-90 1st PLUG @ 3050 ft. w/ 100 SX 2nd PLUG @ 1880 ft. w/ 50 SX 3rd PLUG @ 950 ft. w/ 50 SX 4th PLUG @ 40-0 ft. w/ 10 SX RAT HOLE CIRCULATED W/ 15 SX MOUSE HOLE CIRCULATED W/ 10 SX WATER WELL PLUGGED W/ Off-Set well SX CEMENT COMPANY Halliburton TECHNICIAN MS TYPE OF CEMENT 60/40 6%

Table with 10 columns and 10 rows showing well depth and casing data. Includes values like 5780, 4950, 4620, 4290, 3960, 3630, 3300, 2916, 2640, 2310, 1980, 1650, 1320, 990, 660, 330.

CONSERVATION DIVISION Wichita, Kansas

Mail to: Conservation Division, 200 Colorado Derby Building, 202 W. First St., Wichita, Kansas 67202-1236.

TTD Feb. 10 - 1990

Wichita, Kansas

REMEMBER TO:

- File Drill Pit Application (form CDP-1) with Intent to Drill; File Completion Form ACD-1 within 120 days of spud date; File acreage attribution plat according to field prorated orders; Notify appropriate district office 48 hours prior to workover or re-entry; Submit plugging report (C/P-4) after plugging is completed; Obtain written approval before disposing or injecting salt water.

33W