

1 020764

5-20 API NUMBER 15- 1953 175-00489-0000

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

NW NW NW SE, SEC. 26, T 7, R 31 S, R 33 W/X

2490 feet from S section line
2490 feet from E section line
Federal Farm

TECHNICIAN'S PLUGGING REPORT

Operator License # 5952

Lease Name Mortgage GU D Well # 1

Operator: Amoco Production Company

County Seward

Name & Address P.O. Box 800, Room 925

Well Total Depth 2725 88.56 feet

Denver, CO 80201

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 580

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Amoco Production Company License Number 5952

Address P.O. Box 800, Room 925, Denver, CO 80201

Company to plug at: Hour: 9 a.m. Day: 20 Month: 5 Year: 1994

Plugging proposal received from Richard Jenisch

(company name) Amoco (phone) 316-356-6959

logs: 5 1/2" at 2711' w/900 sx cement. 4" liner 1558-1767'. Perfs at 2628-94'

1st plug sand in to 1613', run tubing to 1611', pump 218 sx cement,

2nd plug pump 220 sx cement with tubing at 1270', circulate cement to surface,

3rd plug pull tubing and fill 5 1/2" to -4'.

Plugging Proposal Received by Glenn Barlow (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 4:30 p.m. Day: 20 Month: 5 Year: 1994

ACTUAL PLUGGING REPORT 1st plug sanded in to 1613', ran tubing to 1611', pumped 218 sx cement-did not circulate, pulled tubing and waited three hours.

2nd plug pumped 220 sx cement with tubing at 1270', circulated cement to surface,

3rd plug pulled tubing and filled 5 1/2" to -4'.

Remarks: Used Class H cement by Halliburton. No casing recovery.

(If additional description is necessary, use BACK of CONSERVATION DIVISION WICHITA, KS

INVOICED

DATE 6-6-94

Signed Glenn Barlow (TECHNICIAN)

INV. NO. 40533

5-20 AUG 11 1994

RECEIVED KANSAS CORPORATION COMMISSION

5-31-94

MAY 31 1994

[Signature]