

TO: 1100270  
STATE CORPORATION COMMISSION

1-04

API NUMBER 15-175-21,093-00-00  
NW SW NW SEC. 35, T 31 S, R 33 W

CONSERVATION DIVISION - PLUGGING SECTION 3630 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 4950 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202 LEASE NAME WILMA MILLER WELL # 1-35

TECHNICIAN'S PLUGGING REPORT COUNTY SEWARD 194.19

OPERATOR LICENSE # 9953 WELL TOTAL DEPTH 5975 FEET

OPERATOR: HARRIS OIL & GAS COMPANY PRODUCTION CSG: SIZE 4 1/2" @ 5180' WITH 100 SX

NAME AND 1125 17TH STREET, SUITE 2290 SURFACE CASING: SIZE 8 5/8" @ 1518' WITH 675 SX

ADDRESS DENVER, CO 80202

ABANDONED OIL WELL X GAS WELL INPUT WELL SWD WELL D/A

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR SARGENT & HORTON PLUGGING, INC LICENSE NUMBER 31151

ADDRESS RT 1, BOX49BA, TYRONE, OK 73951-9731

COMPANY TO PLUG AT: HOUR: 9:30 AM DAY: 30 MONTH: 12 YEAR: 1998

PLUGGING PROPOSAL RECEIVED FROM DON HORTON

(COMPANY NAME) SARGENT & HORTON PLUGGING, INC (PHONE) 580-854-6515

WERE: PERFS AT 4932-42

1ST PLUG SPOT 20 SX CEMENT AND 2 SX HULLS AT 4932-4732.

2ND PLUG AT 3200' WITH 50 SX CEMENT.

3RD PLUG AT 1550' WITH 50 SX CEMENT.

4TH PLUG AT 500' WITH 30 SX CEMENT. 5TH PLUG AT 0-40' WITH 10 SX CEMENT.

PLUGGING PROPOSAL RECEIVED BY SCOTT ALBERG

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL PART X NONE

OPERATIONS COMPLETED: HOUR: 12:00 PM DAY: 04 MONTH: 01 YEAR: 1999

ACTUAL PLUGGING REPORT

1ST PLUG MIXED 200# HULLS AND 20 SX CEMENT AND SPOT PLUG AT 4932-4732'. SHOOT CASING.

ON 1-1-99 2ND PLUG PULL CASING TO 3050'. MIX 50 SX PLUG FROM 3050' TO 2900'.

3RD PLUG PULL CASING TO 1500'. MIX 50 SX PLUG FROM 1500' TO 1400'.

ON 1-4-99 4TH PLUG PULL CASING TO 500' MIX 30 SX PLUG AT 500'.

5TH PLUG PULL CASING TO 40' MIX 10 SX CEMENT TO FILL 40' TO 0'.

REMARKS: USED COMMON CEMENT BY SARGENTS. RECOVERED 3325' OF 4 1/2" CASING.

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM)  
Wichita Kansas

I (DID) OBSERVE THIS PLUGGING.

SIGNED Gary Winters  
(TECHNICIAN) FORM CP-2/3

1-12-99  
60525

RECEIVED  
STATE CORPORATION COMMISSION  
1-8-99  
JAN 8 1999