

To: 1 020665 4-26  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-175-10049-00-01  
Drilled 10/61 R

C SW SW, SEC. 6, T 31 S, R 34 W/E  
660 feet from S section line  
4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT  
Operator License # 5208  
Operator: Mobil Oil Corporation  
Name & Address 2319 N. Kansas  
Liberal, KS 67901

Lease Name Strong Well # 2  
County Seward 187.85  
Well Total Depth 5780 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 639

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_  
Other well as hereinafter indicated Input Well E-NHPT SWD Well D&A  
E-13, 902-0004

Plugging Contractor Sargent & Horton Plugging Inc. License Number 31151  
Address Rt. 1, Box 49BA, Tyrone, OK 73951-9731

Company to plug at: Hour: 2:30 p.m. Day: 23 Month: 4 Year: 19 93

Plugging proposal received from Don Horton  
(company name) Sargent & Horton Plugging Inc. (phone) 405-854-6515

were: 5 1/2" at 5768' w/550 sx cement, PBTD 5520', Perfs at 5703-13', 5562-84', 5306-26'

1st plug run tubing, tag, pump 1 sx hulls and 20 sx cement,

2nd plug pump 20 sx cement at 1780',

3rd plug pump 30 sx cement at 650',

4th plug pump 5 sx cement at 40 to -4'

Plugging Proposal Received by Glenn R. Barlow  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part X None \_\_\_\_\_

Operations Completed: Hour: 6 p.m. Day: 26 Month: 4 Year: 19 93

ACTUAL PLUGGING REPORT 1st plug ran tubing, tagged out at 4605', pumped 1 sx hulls, and 20 sx cement at 4600',

2nd plug pumped 20 sx cement at 1780',

3rd plug pumped 30 sx cement at 650',

4th plug pumped 5 sx cement at 40 to -4'.

Remarks: Used common cement by Sargent & Horton. No casing recovery.  
(If additional description is necessary, use BACK of this form.)

INVOICED  
observe this plugging.

DATE 5-12-93  
INV. NO. 37680  
4-26

Signed Glenn R. Barlow  
(TECHNICIAN) RNL