

To: 1 020860 4-16  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 175-20,018 -0000  
C NE NW, SEC. 7, T. 31 S, R. 34 W/E

TECHNICIAN'S PLUGGING REPORT

Operator License # 5208  
Operator: Mobil Oil Corporation  
Name & Address: 2319 N. Kansas  
Liberal, KS 67901

4620 feet from S section line  
3300 feet from E section line  
Lease Name Marguerite Rooney Well # 3  
County Seward 184.60  
Well Total Depth 5680 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 1722

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well  No Docket # SHD Well \_\_\_\_\_ D&A \_\_\_\_\_  
Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Sargent & Horton Plugging, Inc. License Number 31151  
Address Rt. 1, Box 49BA, Tyrone, OK 73951-9731

Company to plug at: Hour: 2 p.m. Day: 14 Month: 4 Year: 19 93

Plugging proposal received from Don Horton  
(company name) Sargent & Horton Plugging, Inc. (phone) 405-854-6515

were: 4 1/2" at 5511' w/125 sx cement, PBTD 5505', Perfs at 5340-66'  
1st plug pump 20 sx cement at perfs,  
2nd plug pump 40 sx cement at 1750',  
3rd plug pump 30 sx cement at 650',  
4th plug pump 10 sx cement at 40 to -4'.

Plugging Proposal Received by Glenn Barlow (TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part  None \_\_\_\_\_

Operations Completed: Hour: 3 p.m. Day: 16 Month: 4 Year: 19 93

ACTUAL PLUGGING REPORT 1st plug pumped 1 sx hulls and 20 sx cement at perfs,  
2nd plug pumped 40 sx cement at 1750',  
3rd plug pumped 30 sx cement at 650',  
4th plug pumped 10 sx cement at 40 to -4'.  
Mud between all plugs.

Remarks: Used common cement by Sargent & Horton. Recovered 1825' of 4 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

INVOICED  
Observe this plugging.

DATE 4-29-93

Signed Glenn R. Barlow (TECHNICIAN)  
RECEIVED STATE CORPORATION COMMISSION APR 22 4-22-93 CONSERVATION DIVISION WICHITA, KANSAS

WV. NO. 37635 4-16