

To: 1, 100159
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

9-11

API NUMBER 15- 175-21,141-0000

TECHNICIAN'S PLUGGING REPORT

Operator License # 4824

Operator: Mesa Operating Co.
Name:
Address: 5205 N. O'Connor Blvd., Ste. 1400W
Irving, TX 75039

NW NW SE SE, SEC. 7, T 31 S, R 34 W/E
1250 feet from S section line
1250 feet from E section line

Lease Name Central Life Well # 2

County Seward 92.59

Well Total Depth 2849 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 627

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Border-Line, Inc. License Number 7840

Address RR 3, Box 1043, Ulysses, KS 67880-1043

Company to plug at: Hour: 1:30 p.m. Day: 11 Month: 9 Year: 19 97

Plugging proposal received from Tim Lewis

(company name) Mesa Operating Co. (phone) 972-444-9001

logs: 5 1/2" at 2849' w/425 sx cement, PBSD 2798', Perfs at 2164-2224, 2474-2658'

1st plug previously set at 1669' with 50 sx cement,

RECEIVED
KANSAS CORPORATION COMMISSION

2nd plug at 1730' with 80 sx cement,

SEP 17 1997

3rd plug at 650' with 50 sx cement,

4th plug at 40' with 10 sx cement.

CONSERVATION DIVISION
WICHITA, KS
Gary Winters

Plugging Proposal Received by (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 3:30 p.m. Day: 11 Month: 9 Year: 19 97

ACTUAL PLUGGING REPORT 1st plug previously set at 1669' with 50 sx cement,

2nd plug perforated 5 1/2" casing at 525' and pumped 100 sx cement, circulated cement to surface leaving 5 1/2" and 8 5/8" X 5 1/2" annulus full. Cement did not fall.

Remarks: Used Halliburton Lite cement by Halliburton. No casing recovery.
(If additional description is necessary, use BACK of this form.)

I (did / did not) observe this plugging.

DATE 9-23-97

INV. NO. 49082

Signed Gary Winters (TECHNICIAN)