

1 020081

6-3-87

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-175-20,828-60-01  
SE SW, SEC. 35, T 31 S, R 34 W/E  
660 feet from S section line  
3300 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5703  
Operator: J.M. Huber Corporation  
Name & Address 7120 I-40 West, Suite 232  
Amarillo, TX 79106

Lease Name M.A. Johnson Well # 1  
County Seward 184.08  
Well Total Depth 5664 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 9 5/8 feet 1639

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Sargent's Casing Pulling Service License Number 6547

Address 620 South Lincoln, P.O. Box 506, Liberal, KS 67901

Company to plug at: Hour: 11 a.m. Day: 3 Month: 6 Year: 19 87

Plugging proposal received from Doug Blair

(company name) Sargent's Casing Pulling Service (phone) 316-624-7455

were: 5 1/2" at 5660' PBTD 5450' Perfs at 4836-44' DV tool set at 2992' - squeezed 5 1/2" to 2010'  
1st plug pump 1 sx hulls and 20 sx cement at perfs,

2nd plug pump 50 sx cement at 1660',

3rd plug pump 25 sx cement at 850',

4th plug pump 10 sx cement at 40-0'.

Plugging Proposal Received by Paul Luthi  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 4:30 p.m. Day: 3 Month: 6 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug pumped 1 sx hulls and 20 sx cement at perfs,

2nd plug pumped 50 sx cement at 1660',

3rd plug pumped 25 sx cement at 850',

4th plug pumped 10 sx cement at 40-0'. Mud between plugs.

JUN 9 - 1987 6-9-87

CONSERVATION DIVISION  
Wichita, Kansas

Remarks: Used common cement by Sargent's. Recovered 1967' of 5 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

**INVOICED**

DATE 6-9-87

INV. NO. 17200

6-3

Signed Glean R. Barlow  
(TECHNICIAN)