

To: 1 051095
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 025-20,932-00-00
110' E of C
NE NE NW, SEC. 36, T 31 S, R 24 WAK

TECHNICIAN'S PLUGGING REPORT

Operator License # 5703

4950 feet from S section line

2860 feet from E section line

Operator: J.M. Huber Corporation

Lease Name Alley Well # 36-1

Name & Address 7120 I-40 West, Suite 232

County Clark 188.50

Amarillo, TX 79106

Well Total Depth 5800 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 1700

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Bruce Well Service License Number _____

Address Box 1597, Liberal, KS 67901

Company to plug at: Hour: 8 a.m. Day: 12 Month: 10 Year: 19 88

Plugging proposal received from Jerry Trout

(company name) J.M. Huber Corporation (phone) 806-353-9837

were: 5 1/2" at 5798' PBD 5750' Perfs at 5654-57'

1st plug set CIBP at 5635' with 2 sx cement on top,

2nd plug displace hole through tubing with mud, plugged through tubing after pulling casing with 100 sx cement at 1730-1630',

3rd plug at 850' with 50 sx cement, 4th plug at 40' with 10 sx cement.

Plugging Proposal Received by Richard Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part None _____

Operations Completed: Hour: 10:30 a. Day: 12 Month: 10 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug set CIBP at 5635' with 2 sx cement on top,

2nd plug displace hole through tubing with mud, plugged through tubing after pulling casing with 100 sx cement at 1730-1630',

3rd plug at 850' with 50 sx cement,

4th plug at 40' with 10 sx cement.

Remarks: Used Class H cement by Halliburton. Recovered 2800' of 5 1/2" casing.

(if additional description is necessary, use BACK of this form.)

INVOICED
(if applicable) observe this plugging.

DATE 10-27-88

Signed Richard W. Lacey
(TECHNICIAN)

INV. NO. 27781