

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-025-00058-00-01  
Spot: CSWSW Sec/Twnshp/Rge: 6-31S-25W  
660 feet from S Section Line, 630 feet from W Section Line  
Lease/Unit Name: HOUSER Well Number: 1-6 RE  
County: CLARK Total Vertical Depth: 3650 feet

Operator License No.: 32200  
Op Name: CIRRUS PRODUCTION CO.  
Address: 201 N. GRAND STE. 200  
ENID, OK 73702

Conductor Pipe: Size \_\_\_\_\_ feet: \_\_\_\_\_  
Surface Casing: Size 8.625 feet: 2701  
Production: Size 4.5 feet: 3450  
Liner: Size \_\_\_\_\_ feet: \_\_\_\_\_

8118.63

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 09/28/2001 10:30 AM  
Plug Co. License No.: 32722 Plug Co. Name: KERR WELL SERVICE, INC.  
Proposal Rcvd. from: TOMMY DISEKET Company: CIRRUS PRODUCTION Phone: (580) 237-0002

Proposed Plugging Method: SET CIBP @ 3300' & 2 SX CMT. 1ST PLUG AT 2700' WITH 50 SX CMT. 2ND PLUG AT 700' WITH 30 SX CMT. 3RD PLUG AT 40-0' WITH 10 SX CMT.

Plugging Proposal Received By: STEVE DURRANT Witness Type: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 09/28/2001 3:30 PM KCC Agent: STEVE MIDDLETON

Actual Plugging Report:

SET CIBP @ 3280' WITH 2 SX CMT ON TOP. 1ST PLUG PULL CASING OUT OF HOLE. RUN TUBING TO 2701' & SPOT 50 SX CMT. 2ND PLUG PULL TO 700' & SPOT 30 SX CMT. 3RD PLUG PULL TUBING TO 30 & SPOT 10 SX CMT.

Remarks: USED 60/40 POZMIX 6% GEL BY HALLIBURTON. RECOVERED 2700' OF 4 1/2" CASING.

Plugged through: TBG

District: 01

Signed \_\_\_\_\_



(TECHNICIAN)

RECEIVED

OCT 05 2001

KCC WICHITA

INVOICED

OCT 02 2001

DATE 10-05-01

INV. NO. 2002060739



Form CP-2/3