

1 050679

API NUMBER 15-151-21,720 ⁰⁰⁻⁰⁰ R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION SE
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

SW NE, SEC. 18, T 28 S, R 12 W 1/2
2970 feet from S section line

1650 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5027

Lease Name Hessel "B" Well # 2

Operator: J. A. Allison

County Pratt 96.20

Name & Address 300 West Douglas

Well Total Depth 2960 feet

305

Conductor Pipe: Size _____ feet

Wichita KS 67202

Surface Casing: Size 10 3/4 feet 263

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A

Other well as hereinafter indicated _____

Plugging Contractor Union Drilling Company License Number 5103

Address 422 Union Center Bldg. Wichita KS 67202

Company to plug at: Hour: 12:00 noon Day: 12 Month: October Year: 19 85

Plugging proposal received from Jim Allison

(company name) J. A. Allison (phone) 316-263-2241

work: keep hole full of heavy mud + spot cement plugs
through drill pipe. 1st plug @ base of the Anhydrite
with 50sx. 2nd plug @ 330' w/40sx. 3rd plug @ 40'
with a solid bridge plug + 10sx of cement. 4th plug
circulate rathole with 10sx of cement

Plugging Proposal Received by Richard W. Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None

Operations Completed: Hour: 2:00 pm Day: 12 Month: October Year: 19 85

ACTUAL PLUGGING REPORT Kept hole full of heavy mud + spotted cement

plugs through drill pipe. 1st plug @ 770' w/50sx

2nd plug @ 330' w/40sx

3rd plug @ 40' w/SBP + 10sx

Circulate rathole w/10sx

Anhydrite 770 base Elevation 1860 GL

Remarks: Allied pumped 60/40 pozmix 6% gel cement

(If additional description is necessary, use BACK of this form.)

INVOICED

DATE NOV 22 1985

INV. NO. 11100

RECEIVED
STATE CORPORATION COMMISSION

NOV 18 1985

Signed Richard W. Lacey
(TECHNICIAN)