

1 080498

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 151-21,541-00-60  
430' W of  
C N/2 NE, SEC. 19, T28 S, R 12 W/8

4620 feet from S section line  
1750 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5027

Lease Name Bertram Well # 1

Operator: J. A. Allison  
Name & Address: 300 West Douglas, Suite 305  
Wichita, KS 67202

County Pratt 97.31

Well Total Depth 2994 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 13 3/8" feet 206

Abandoned Oil Well \_\_\_\_\_ Gas Well  Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling License Number 6050

Address P. O. Box 347, Chase, KS 67524

Company to plug at: Hour: 10:30 am Day: 21 Month: March Year: 19 86

Plugging proposal received from Vernon Dumtz

(company name) Kelso (phone) 316-938-2457

were: 4 1/2" at 2989' PBD 2968' Perfs at 2934-40'

1st plug pump 1 sack hulls and 25 sx cement to bottom

2nd plug squeeze well with 3 sx hulls, 15 sx gel 50 sx cement, 10 sx gel, 1 sack hulls, and 150 sx cement.

Plugging Proposal Received by Richard W. Lacey  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 11:15 am Day: 21 Month: March Year: 19 86

ACTUAL PLUGGING REPORT 1st plug pumped 1 sack hulls and 25 sx cement to bottom, 2nd plug squeezed well with 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls and 150 sx cement.

Maximum pressure 100 psi and shut in 0

Remarks: Recovered 2100' 4 1/2" casing. Used 60/40 Pozmix 6% gel by Allied.  
(If additional description is necessary, use BACK of this form.)

(If possible) observe this plugging.

Signed J. H. McD (TECHNICIAN)

INVOICED

DATE APR 1 1986

INV. NO. 13225

3-31-86 MAR 31 1986