

1040415

4-19

1990

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-151-21,862-00-00

SW SW NE, SEC. 10, T 28 S, R 12 W
2970 feet from S section line
2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4059

Lease Name Rosenbaum Well # 1

Operator: Devonian Oil Company

County Pratt 145.60

Name & Address 1246 Mass

Well Total Depth 4480 feet

Lawrence, KS 66044

Conductor Pipe: Size 10 3/4 feet 246

Surface Casing: Size 8 5/8 feet 852

Abandoned Oil Well Gas Well Input Well SMD Well O&A

Other well as hereinafter indicated

Plugging Contractor Pratt Well Service, Inc. License Number 5893

Address P.O. Box 847, Pratt, KS 67124

Company to plug at: Hour: 2:30 p.m. Day: 24 Month: 1 Year: 19 90

Plugging proposal received from Bruce Wagner

(company name) Pratt Well Service, Inc. (phone) 316-672-2531

were: 4 1/2" at 4480' PBDT 3992' Perfs at 3972-76, 3964-70'

1st plug sand back to 3920' and dump 4 sx cement on top of sand through bailer,
2nd plug pump 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"
wiper plug and pump 100 sx cement.

Plugging Proposal Received by Duane Rankin (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 2:00 p.m. Day: 19 Month: 4 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug sanded back to 3875' and dumped 4 sx cement on top of sand bridge with bailer,

2nd plug pumped down 8 5/8" surface pipe with 400 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement.

Maximum pressure 300 psi and shut in 100 psi.

4/19/90 Topped out 8 5/8" with 10 sx cement. (over)

Remarks: Used 60/40 Pozmix-6% gel by B.J. Titan. Recovered 1508' of 4 1/2" casing. (If additional description is necessary, use BACK of this form.)

INVOICED
DATE 5-3-90
INV. NO. 28020

APR 30 1990
04-30-90
Conservation Division
Wichita, Kansas

Signed Stephen J. Pfeiffer (TECHNICIAN)

CONT: 4/19/90

3rd plug pumped down 10. 3/4" X 8 5/8" annulus with 100. sx cement. Maximum pressure 300 psi and shut in 200 psi.

RECEIVED

DATE

BY