

1 020294

2-15 15-129-3011-0000

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-Drill Completion Date 10/27/66

NW SE SW, SEC. 27, T 31 S, R 42 W/E
990 feet from S section line
3630 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 3538

Lease Name Clancy A Well # Unit 1

Operator: Graham Royalty LTD.
Name & Address: P.O. Box 919
Liberal, KS 67905-0919

County Morton 169.81

Well Total Depth 5225 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 1413

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Sargent's Casing Pulling Service License Number 6547

Address P.O. Box 506, Liberal, KS 67905-0506

Company to plug at: Hour: 2:30 p.m. Day: 14 Month: 2 Year: 19 90

Plugging proposal received from Don Horton

(company name) Sargent's Casing Pulling Service (phone) 316-624-7455

were: 4 1/2" at 5046' PBD 5015' Perfs at 4870-77, 4882-92, 4904-13, 4922-27'

1st plug pump 20 sx cement at perforations with tubing,
shoot pipe off at 1475', load hole with mud,

2nd plug pump 40 sx cement at 1440',

3rd plug pump 35 sx cement at 700', 4th plug pump 10 sx cement at 35-0'.

Plugging Proposal Received by Glenn R. Barlow (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 3:45 p.m. Day: 15 Month: 2 Year: 1990

ACTUAL PLUGGING REPORT 1st plug pumped 20 sx cement at perforations with tubing,
shot off pipe at 1475', loaded hole with mud,

2nd plug pumped 40 sx cement at 1440',

3rd plug pumped 35 sx cement at 700',

4th plug pumped 10 sx cement at 35-0'.

RECEIVED
STATE CORPORATION COMMISSION
FEB 21 1990
2-21-90

CONSERVATION DIVISION
WICHITA, KANSAS

Remarks: Used common cement by Sargent's. Recovered 1475' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 2-23-90

INV. NO. 27552

observe this plugging.

Signed Glenn R. Barlow MS (TECHNICIAN)