

1051900 2-16

API NUMBER 15- 119-20,943 -0000

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

C N/2 SW, SEC. 3, T 32 S, R 30 W/E  
1980 feet from S section line  
1320 feet from W E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4782  
Operator: Ensign Operating Co.  
Name & Address: P.O. Box 2161  
Liberal, KS 67905-2161

Lease Name Koehn Well # 1-3  
County Meade  
Well Total Depth 6150 199.88 feet  
Conductor Pipe: Size feet  
Surface Casing: Size 8 5/8 feet 1599

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Duke Drilling Company, Inc. License Number 5929

Address 310 W. Central, Ste. 202, Wichita, KS 67202

Company to plug at: Hour: Day: 16 Month: 2 Year: 19 95

Plugging proposal received from Reed Wacker

(company name) Ensign Operating Co. (phone) 316-626-8131

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 1630' with 50 sx cement, 2nd plug at 600' with 40 sx cement,  
3rd plug at 40' with 10 sx cement,

4th plug to circulate rathole with 15 sx cement,

5th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 8 p.m. Day: 16 Month: 2 Year: 19 95

ACTUAL PLUGGING REPORT 1st plug at 1630' with 50 sx cement,

2nd plug at 600' with 40 sx cement,

3rd plug at 40' with 10 sx cement,

4th plug to circulate rathole with 15 sx cement,

5th plug to circulate mousehole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Halliburton.  
(if additional description is necessary, use BACK of this form.)

INVOICED (did not observe this plugging.)

DATE 2-28-95

INV. NO. 42305

Signed Richard M. Lacey (TECHNICIAN)

STATE CORPORATION COMMISSION RECEIVED FEB 29 1995

EFFECTIVE DATE: 1-25-95

State of Kansas 15

NOTICE OF INTENTION TO DRILL

119-20,943-0000

Must be approved by the K.C.C. five (5) days prior to commencing well

Expected Spud Date Feb. 1, 1995 month day year

Spot C N/2 SW/4 Sec 3 Twp 32 S. Rg 30 East

OPERATOR: License # 04782 Name: Ensign Operating Co. Address: P.O. Box 2161 Liberal, KS 67905-2161

1980 feet from south line of Section 1320 feet from east line of Section IS SECTION X REGULAR IRREGULAR

(NOTE: Locate well on the Section Plat on Reverse Side) County: Meade Lease Name: Koehn Well #: 1-3 Field Name: Wildcat

CONTRACTOR: License #: Unknown Name: Advise on ACO-1 RUPP #4

Is this a Prorated/Spaced Field? yes X no Target Formation(s): Morrow Nearest lease or unit boundary: 1320'

Well Drilled For: Well Class: Type Equipment: Oil Gas OAWO Seismic; Other Enh Rec Storage Disposal # of Holes Infield Pool Ext. Wildcat Other Mud Rotary Air Rotary Cable

Ground Surface Elevation: 2762 feet MSL Water well within one-quarter mile: yes no Public water supply well within one mile: yes no Depth to bottom of fresh water: 520' Depth to bottom of usable water: 580'

If OAWO: old well information as follows: Operator: Well Name: Comp. Date: Old Total Depth

Surface Pipe by Alternate: X 1 Length of Surface Pipe Planned to be set: 1675' Length of Conductor pipe required: None Projected Total Depth: 6,000'

Directional, Deviated or Horizontal wellbore? yes X no If yes, true vertical depth: Bottom Hole Location:

Formation at Total Depth: Miss Water Source for Drilling Operations: DWR Permit #: Apply to DWR for Permit Will Cores Be Taken? yes X no

Exp. 7/20/95

AFFIDAVIT

600' Alt. I Req.

The undersigned hereby affirms that the drilling, completion and eventual plugging of this well will comply with K.S.A. 55-101, et. seq. It is agreed that the following minimum requirements...

Pusher: Reed Wacker INIT: R.L. SPUD DATE: 2-2-95 LENGTH SURFACE PLANNED: 1599 RESERVE PIT STATUS- REMOVE FLUID LINED after salt sect. bbls. when done bbls. RATHOLED AHEAD? Y N SIZE HOLE SURFACE PIPE @ CONDUCTOR ANHYDRITE T- B- ELEVATION TD 6150 FORMATION 6200 RAN PIPE @ DV TOOL ALT II DONE SX Y N SX SX Arbuckle Plug @ Ft. W/ SX SX Hug./Council @ Ft. W/ SX SX Anhydrite Base @ 1630 Ft. W/ 50 SX 1/2 Base Anyh. @ 600 Ft. W/ 40 SX 1/2, 1/2 Plug @ Ft. W/ SX SX Bottom Surface @ Ft. W/ SX SX 40' Plug @ 40 Ft. W/ 10 SX RAT HOLE CIRC/W 15 SX MOUSE HOLE W/ 10 SX WATER WELL SX (Irr. Well Fond Hauling) TECHNICIAN R.L. DATE 2-14-95 TYPE OF CEMENT 60/40 per 60% STARTING TIME (AM/PM) DATE COMPLETION TIME (AM/PM) DATE 2-16 CEMENT COMPANY RECEIVED STATE CORPORATION COM. 1995