

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-119-20766-00-00
Spot: CNWNE Sec/Twnshp/Rge: 30-32S-29W
4620 feet from S Section Line, 1980 feet from E Section Line
Lease/Unit Name: ANGELL Well Number: 1
County: MEADE Total Vertical Depth: 5694 feet

Operator License No.: 31093
Op Name: BECKER OIL CORPORATION
Address: 122 E. GRAND, STE. 212
PONCA CITY, OK 74601

Conductor Pipe: Size feet: \$185.06
Surface Casing: Size 8.625 feet: 1691 WITH 655 SX CMT
Production: Size 5.5 feet: 5692 WITH 275 SX CMT
Liner: Size feet:

Well Type: GAS UIC Docket No: Date/Time to Plug: 05/07/2002 9:35 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.

Proposal Rcvd. from: Company: Phone:

Proposed Plugging Method: SAND TO 5549' & 5 SX CMT. 1ST PLUG AT 1720' WITH 50 SX CMT. 2ND PLUG AT 400' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT. USE 10 SX GEL FOR SPACER.

Plugging Proposal Received By: JIM HOLLAND Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 05/08/2002 11:40 AM KCC Agent: STEVE DURRANT

Actual Plugging Report:

PBTD 5655'. PERFS AT 5603-14'. SAND TO 5549' & 5 SX CMT. 1ST PLUG PUMP 30 BBL WATER, 10 SX GEL, & 50 SX CMT AT 1720'. 2ND PLUG AT 400' WITH 50 SX CMT. 3RD PLUG AT 40-0' WITH 10 SX CMT.

RECEIVED

MAY 13 2002

KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 2830' OF 5 1/2" CASING.

Plugged through: CSG

District: 01

Signed Steve Durrant
(TECHNICIAN)

INVOICED MAY 09 2002
DATE 5-14-02
INV. NO. 2002061773