

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-189-20702-00-02  
Spot: CNW Sec/Twnshp/Rge: 25-31S-35W  
1320 feet from N Section Line, 1320 feet from W Section Line  
Lease/Unit Name: LOWE 1-A UNIT Well Number: 2  
County: STEVENS Total Vertical Depth: 3200 feet

Operator License No.: 5208  
Op Name: EXXONMOBIL OIL CORP  
Address: PO BOX 4358  
HOUSTON, TX 77210

Conductor Pipe: Size feet: 8104.00  
Surface Casing: Size 8.625 feet: 1784 WITH 680 SX CMT  
Production: Size 5.5 feet: 3188 WITH 455 SX CMT  
Liner: Size feet:

Well Type: GAS UIC Docket No: Date/Time to Plug: 12/03/2001 2:00 PM  
Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.  
Proposal Rcvd. from: DON HORTON Company: SARGENT AND HORTON PLUGGIN Phone: (580) 854-6515

Proposed Plugging Method: SET CIBP @ 2650' WITH 2 SX CMT. 1ST PLUG AT 1810' WITH 25 SX CMT. 2ND PLUG AT 550' CMT TO SURFACE.

Plugging Proposal Received By: SCOTT ALBERG WitnessType: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 12/03/2001 6:00 PM KCC Agent: JIM HOLLAND

Actual Plugging Report:

PBTD 3130'. PERFS AT 2988-3024, 2685-2775'. PULLED 4" STRETCH ON 5 1/2, CMT TO 400'. CIBP @ 2950' WITH 2 SX CMT PER EXXON MOBIL RECORDS. SET CIBP @ 2635' WITH 2 SX CMT ON TOP. 1ST PLUG RUN IN HOLE WITH TUBING TO 1810'. LOAD HOLE WITH MUD. SPOT 32 SX CMT, DISPLACE WITH MUD. 2ND PLUG PULL OUT OF HOLE WITH TUBING TO 550'. LOAD HOLE WITH MUD & PUMP 62 SX CMT TO SURFACE. PUMP 13 SX CMT DOWN BACKSIDE AND PRESSURE TO 330#.

Remarks: USED COMMON CEMENT BY SARGENTS. NO CASING RECOVERED.

Plugged through: TBG

District: 01

RECEIVED

DEC 19 2001

KCC WICHITA

Signed

Jim Holland  
(TECHNICIAN)

INVOICE

DEC 07 2001

~~DEC 06 2001~~

DATE 12-20-01

INV. NO. 2002061280MP

Form CP-2/3