

1080209

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 189-20,749-0000

W/2 W/2 SE, SEC. 24, T 31 S, R 35 W/X
1320 feet from N SE Corner of XXX section line
2310 feet from W SE Corner of XXX section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5298

Lease Name Anna Lowe Well # 1

Operator: Mobil Oil Corporation

County Stevens

Name & Address P. O. Box 5444

Well Total Depth 5845 189.96 feet

Denver, CO 80217

Conductor Pipe: Size _____ feet

Surface Casing: Size 9 5/8 feet 1730

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SHD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Unit Drilling & Exploration Co. License Number 9137

Address Tulsa, OK

Company to plug at: Hour: 10:00 pm Day: 3 Month: September Year: 19 84

Plugging proposal received from J..L. Douglass

(company name) Mobil (phone) 303-298-2047

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 4675' with 50 sx cement 2nd plug at 1830' with 125 sx cement

3rd plug at 850' with 115 sx cement 4th plug at 850' with 50 sx cement
solid bridge

5th plug hulls - 9 5/8" plug at 40' -- cement to surface with 15 sx cement

7th plug to circulate rat hole with 10 sx cement

8th plug to circulate mouse hole with 10 sx cement

Plugging Proposal Received by J. H. Metz
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 2:15 am Day: 4 Month: September Year: 19 84

ACTUAL PLUGGING REPORT 1st plug at 4675' with 50 sx cement, 2nd plug at 1830' with

125 sx cement, 3rd plug at 850' with 115 sx cement, 4th plug at 850' with 50 sx cement,

5th & 6th plugs - solid bridge - hulls - 9 5/8" plug at 40' -- cement to surface with

15 sx cement, 7th plug to circulate rat hole with 10 sx cement, 8th plug to circulate

mouse hole with 10 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

SEP 17 1984

Remarks: Used Class H Cement with 3% cc by Halliburton
(If additional description is necessary, use BACK of this form.)

CONSERVATION DIVISION
Wichita, Kansas

INVOICED
date / did not observe this plugging.

DATE 9-26-84

Signed J. H. Metz (TECHNICIAN)

INV. NO. 3854