

1100017

To: STATE CORPORATION COMMISSION
Wichita State Office Bldg. PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15- 119-20,403-0000

SE SE SE, SEC. 24, T 32 S, R 30 W/X

330 feet from S section line

330 feet from E section line

2-12

TECHNICIAN'S PLUGGING REPORT

Operator License # 6528

Lease Name Ramsey Well # 1

Operator: R.J. Patrick Operating Co.

County Meade

Name: P.O. Box 1314

Well Total Depth 6055 196.79 feet

Address: Liberal, KS 67905-1314

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 1680

Abandoned Oil Well Gas Well X Input Well SWD Well O&A

Other well as hereinafter indicated

Plugging Contractor Sargent's Casing Pulling Service License Number 6547

Address: P.O. Box 506, Liberal, KS 67905-0506

Company to plug at: Hour: 1 p.m. Day: 12 Month: 2 Year: 1996

Plugging proposal received from Kirby Lillard

(company name) Sargent's Casing Pulling Service (phone) 316-624-7455

logs: 4 1/2" at 6053' w/350 sx cement, PBTD 5736', Perfs at 5860-64, 5606-10'

1st plug pump 1 sx hulls and 20 sx cement to bottom,

2nd plug at 1700' with 50 sx cement,

3rd plug at 500' with 40 sx cement,

4th plug at 40' with 10 sx cement.

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 5 p.m. Day: 12 Month: 2 Year: 1996

ACTUAL PLUGGING REPORT 1st plug pumped 20 sx cement with 100 lbs. hulls at 6000'

2nd plug spotted 50 sx cement at 1700',

3rd plug spotted 40 sx cement at 500';

4th plug spotted 10 sx cement at 40-0'.

2-20-96

RECEIVED KANSAS CORP COMM 1996 FEB 20 A 11:28

Remarks: Used common cement by Sargent's. Recovered 3042' of 4 1/2" casing.

If additional description is necessary, use BACK of this form.)

I (did ~~not~~) observe this plugging.

DATE 2-28-96

Signed Gary Lacey (TECHNICIAN)

INV. NO. 44901

2-12