

To: 1100090
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15- 119-20,970-0000 *corrected*
2/3

TECHNICIAN'S PLUGGING REPORT
Operator License # 4549
Operator: Anadarko Petroleum Corporation
Name: _____
Address: P.O. Box 351
Liberal, KS 67905-0351

C NE SW, SEC. 24, T 32 S, R 30 W/4
1980 feet from S section line
1980 feet from WX section line
Lease Name Fox I Well # 1
County Meade
Well Total Depth 6150 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 15.53

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ O&A _____

Other well as hereinafter indicated _____
Plugging Contractor Sargent & Horton Plugging, Inc. License Number 31151
Address Rt. 1, Box 49BA, Tyrone, OK 73951-9731

Company to plug at: Hour: 9 a.m. Day: 24 Month: 1 Year: 19 97

Plugging proposal received from Don Horton
(company name) Sargent & Horton Plugging, Inc. (phone) 405-854-6515

were: 5 1/2" at 5916', PBD 5870', Perfs at 5842-52'

- 1st plug pump 2 sx hulls and 25 sx cement on bottom.
- 2nd plug at 3100' with 30 sx cement,
- 3rd plug at 1630' with 50 sx cement,
- 4th plug at 650' with 40 sx cement, 5th plug at 40' with 10 sx cement.

Plugging Proposal Received by Gary Winters (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part None _____

Operations Completed: Hour: 5 p.m. Day: 25 Month: 1 Year: 19 97

ACTUAL PLUGGING REPORT 1st plug pumped 2 sx hulls and 25 sx cement from 5842-5642',
2nd plug pumped 30 sx cement at 3100',
3rd plug pumped 50 sx cement at 1630',
4th plug pumped 40 sx cement at 650',
5th plug pumped 10 sx cement at 40'.

Remarks: Used common cement by Sargent & Horton. Recovered 3125' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED

(did / ~~not~~) observe this plugging.

DATE 2-5-97
INV. NO. 47488

Signed *Gary Winters* (TECHNICIAN)