

To: 1 060176 8-19
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-119-20,867-0000
C SE SW, SEC. 24, T. 32 S, R. 30 W X

TECHNICIAN'S PLUGGING REPORT

Operator License # 30444
Operator: Charter Production Company
Name & Address 224 E. Douglas, Ste. 400
Wichita, KS 67202

660 feet from S section line
1980 feet from W X section line
Lease Name Boyd Fox "A" Well # 1
County Meade
Well Total Depth 6075 197.43 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 1634

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X
Other well as hereinafter indicated _____

Plugging Contractor Murfin Drilling Company License Number 30606
Address 250 N. Water, Ste. 300, Wichita, KS 67202

Company to plug at: Hour: 12 p.m. Day: 19 Month: 8 Year: 19 93

Plugging proposal received from Bill Wynn
(company name) Murfin Drilling Company (phone) 316-267-3241

work: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1498-1538'
1st plug at 3050' with 100 sx cement, 2nd plug at 1550' with 50 sx cement,
3rd plug at 600' with 50 sx cement, 4th plug at 40' with 10 sx cement,
5th plug to circulate rathole with 15 sx cement,
6th plug to circulate mousehole with 10 sx cement.

_____ Plugging Proposal Received by Case Morris
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X
Operations Completed: Hour: 6:15 p.m. Day: 19 Month: 8 Year: 19 93

ACTUAL PLUGGING REPORT 1st plug at 3050' with 100 sx cement,
2nd plug at 1650' with 50 sx cement,
3rd plug at 600' with 50 sx cement,
4th plug at 40' with 10 sx cement,
5th plug to circulate rathole with 15 sx cement,
6th plug to circulate mousehole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied.
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE AUG 30 1993
CCL NO. 38500
8-19

RECEIVED
STATE CORPORATION COMMISSION
AUG 24 1993 8-24-93
CONSERVATION DIVISION
Wichita, Kansas

Signed Case Morris
(TECHNICIAN)

EFFECTIVE DATE: 6-7-93
DISTRICT #
SCA7, No

State of Kansas
NOTICE OF INTENTION TO DRILL 119-20,867

FORM MUST BE SIGNED
ALL BLANKS MUST BE FILLED

Must be approved by the K.C.C. five (5) days prior to commencing well

Expected Spud Date 6 22 93
month day year

Spot C SE SW Sec 24 Twp 32 S. Rg 30 East West

OPERATOR: License # 30444
Name: Charter Production Company
Address: 224 E. Douglas, Suite 400
City/State/Zip: Wichita, KS 67202
Contact Person: Jerald W. Rains
Phone: (316) 264-2808

660 feet from South / North line of Section
1980 feet from East / West line of Section
IS SECTION X REGULAR IRREGULAR

CONTRACTOR: License #: 5141
Name: Zenith Drilling Corporation
Martin

(NOTE: Locate well on the Section Plat on Reverse Side)
County: Meade

Well Drilled For: Well Class: Type Equipment:
Oil Enh Rec Infield Mud Rotary
Gas Storage Pool Ext. Air Rotary
OWHO Disposal Wildcat Cable
Seismic: # of Holes Other

Lease Name: Boyd Fox "A" Well #: 1
Field Name: Wildcat
Is this a Prorated/Spaced Field? yes X no

If OWHO: old well information as follows:
Operator:
Well Name:
Comp. Date: Old Total Depth

Target Formation(s): St. Louis
Nearest lease or unit boundary: 330'
Ground Surface Elevation: 2724 feet MSL

Directional, Deviated or Horizontal wellbore? yes X no
If yes, true vertical depth:
Bottom Hole Location:
Exp. 12/9/93

Water well within one-quarter mile: X yes no
Public water supply well within one mile: yes X no
Depth to bottom of fresh water: 400'

Depth to bottom of usable water: 480'
Surface Pipe by Alternate: X 1
Length of Surface Pipe Planned to be set: (1625') 520'

Length of Conductor pipe required: NA
Projected Total Depth: 6100'
Formation at Total Depth: St. Louis

Water Source for Drilling Operations:
X well farm pond other
DWR Permit #:
Will Cores Be Taken? yes X no
If yes, proposed zone:

AFFIDAVIT

520' Alt. I Req.

The undersigned hereby affirms that the drilling, completion and eventual plugging of this well will comply with K.S.A. 55-101, et. seq.
It is agreed that the following minimum requirements will be met:

Pusher B:11
SPUD DATE 8-2-93 INIT. CM
LENGTH SURFACE PLANNED 1625'
RESERVE PIT STATUS- REMOVE FLUID LINED
after salt sect. bbls. when done bbls.
RATHOLED AHEAD? Y N SIZE HOLE
SURFACE PIPE 5 3/4 @ 1624 CONDUCTOR
ANHYDRITE T-1493 B-1538 ELEVATION
TD 6075 FORMATION
RAN PIPE @ DV TOOL ALT II DONE
SX SX Y N
Arbuckle Plug @ Ft. W/ SX
Hug./Council @ 3050 Ft. W/ 100 SX
Anhydrite Base @ 1650 Ft. W/ 50 SX
1/2 Base any @ Ft. W/ SX
1/2 Plug 600 Ft. W/ 50 SX
Bottom Plug @ Ft. W/ SX
40' Plug @ 40 Ft. W/ 10 SX
RAT HOLE CIRC/W 15 SX MOUSE HOLE W/ 10 SX
WATER WELL SX (Irr. Well Pond Hauling)
TECHNICIAN CM DATE 8-10-93
TYPE OF CEMENT 60/40 625
STARTING TIME 12:00 (AM/PM) DATE 8-19-93
COMPLETION TIME 6:15 (AM/PM) DATE 8-19-93
CEMENT COMPANY Allied

RECEIVED
AUG 22 1993
CONSERVATION DIVISION
Wichita, Kansas
STATE COMMISSION