

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
200 Colorado Derby Building
Wichita, Kansas 67202

6-11

2-

*Succent Count
SE SE SW*

API NUMBER: 15-173-20,455-0000

SW SE SW, SECTION 14 TOWNSHIP 29 RANGE 2W

OPERATOR LICENSE # 3581 330 FEET FROM S SECTION LINE
3630 FEET FROM E SECTION LINE

OPERATOR Red Oak Energy Inc.
NAME & 200 W. Douglas Suite 510
ADDRESS Wichita, KS 67202

LEASE NAME: Lauer #1

COUNTY: Sedgwick *116.67*

WELL TOTAL DEPTH: 3590' *PB 2978'*

CONDUCTOR PIPE: _____

SURFACE CASING: 8-5/8" @ 418'

ABANDONED OIL WELL _____ GAS WELL INPUT WELL _____ SMD _____ D&A _____

OTHER WELL AS HEREINAFTER INDICATED: _____

PLUGGING CONTRACTOR: Val Energy Inc.
ADDRESS: Box 322, Haysville, KS 67060 LICENSE: 5822

COMPANY TO PLUG AT: HOUR: 13:30 DAY: 11 MONTH: 6 YR: 1993

PLUGGING PROPOSAL RECEIVED FROM: KCC District 2

COMPANY NAME: Allied Cmtng PHONE: 319-886-5926

WERE: Sand back from 2646' to 2596' -Spot 4sx cmt at 2596' -
Shoot pipe -pull csq to 450' -spot 35sx at 450' -pull
csq to 250' -Circ cmt to surface -pull csq out of hole
-top off w/ cmt.

PLUGGING PROPOSAL RECEIVED BY: Todd Allen

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL () PART () NONE ()

COMPLETED: HOUR: 14:30 DAY: 11 MONTH: 6 YEAR: 1993

ACTUAL PLUGGING REPORT:

Sanded back from 2740' to 2370' -Spotted 55sx cmt at
2370' -shot pipe at 1820' -pulled csq to 450' -spotted
35sx cmt at 450' -pulled csq to 250' -circ cmt to
surface -pulled csq out of hole -topped off w/ cmt.
110sx cmt 60/40 4% gel 50# Hulls on 35sx spot

REMARKS: Allied #2922

I DID OBSERVE THIS PLUGGING.

INVOICED

DATE JUL 13 1993
QTY. NO. 38099

Jerry Clark
Jerry Clark AD (AGENT)