

15-173-19093-0001

2 060283

To:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

RECEIVED  
STATE CORPORATION COMMISSION  
WICHITA, KANSAS

API NUMBER 15- old well  
NENESW, SEC. 2, T 29 S, R 2 W/EX

TECHNICIAN'S PLUGGING REPORT

7-22-85

Operator License # 6679

Lease Name Struthers Well # 1 SWD

Operator: W.D. Short

County Sedgwick 35.00

Name & Address Box 45

Well Total Depth 412 feet

Oxford, KS

Conductor Pipe: Size 4 1/2 feet 231

Surface Casing: Size 8 5/8 feet

Abandoned Oil Well Gas Well Input Well SWD Well XX D&A

Other well as hereinafter indicated

Plugging Contractor W.D. Short License Number

Address

Company to plug at: Hour: Day 15 Month: 7 Year: 19 85

Plugging proposal received from W.D. Short

(company name) (phone)

were: new tubing for 300 feet--circulate full of cement-- 4 1/2" cement to surface

Plugging Proposal Received by District office (TECHNICIAN)

Plugging Operations attended by Agent?: All XX Part None

Operations Completed: Hour: 11:00p.m Day: 15 Month: 7 Year: 19 85

ACTUAL PLUGGING REPORT 4 1/2" bridge off at approximately 125 feet--Hammered on bridge--solid.

Circulated cement to surface and 6-inched over 4 1/2" in collar--approximately 12-15 sacks of cement

Used W.D. Short's cement equipment.

Remarks: (If additional description is necessary, use BACK of this form.)

INVOICED

(d) of (XXXXXX) observe this plugging.

DATE 7-24-85

INV. NO. 9104

Signed [Signature] & [Signature] (TECHNICIAN)

Re

## Oil/Gas Regulation and Water Protection



## Joint Oil/Gas Regulatory Offices



DISTRICT 2  
SUITE 202, CENTURY PLAZA BUILDING  
111 W. DOUGLAS, WICHITA, KS. 67202  
(316) 265-3181

RALPH E. O'CONNOR, DISTRICT GEOLOGIST  
WARREN KIRKPATRICK, FIELD SUPERVISOR  
316-262-8330

Re: Struthers SWD #1

I find that three wells were drilled on this lease. One was plugged by Pickrell Drilling Company, and the other was plugged by W.D. Short. The remaining well was a lost circulation well that was never completed.

In 1957 Pickrell Drilling made a shallow disposal well out of this hole. It has been abandoned for several years. W.D. Short went in, at our request, and plugged this well on July 15, 1985.

Warren Kirkpatrick

A handwritten signature in dark ink, appearing to be "W.K.", is written below the typed name.

Ro

July 9, 85

State Corp. Commission  
Warren Kirkpatrick

Dear Warren:

The enclosed well log is the best I can do. Would you check the files at K.C.C. under my name and Pickens Delg. Co. and see if you can find the original application for S.W.D. and get a copy of the well log?

I have enclosed a letter of 4/17/57 that the K.C.C. didn't have a well log in the application.

Thanks  
Bill Short



STATE OF KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
211 NORTH BROADWAY  
WICHITA 2, KANSAS

January 17, 1957

PICKRELL DRILLING COMPANY  
STRUTHERS "A" LEASE  
CHAMBERS-NORTHEAST MISSISSIPPI FIELD  
WELL NO. SWD #1  
SW/4 of Sec. 2-29-2W  
SEDGWICK COUNTY, KANSAS  
DISPOSAL OF SALT WATER

Pickrell Drilling Company  
705 Fourth National Bank Bldg.  
Wichita, Kansas

Gentlemen:

Enclosed is an attested copy of the above described order together with an invoice of our charges.

Immediately upon the commencement of this disposal operation, please notify this division of the date thereof. Notice also must be given when disposal operations are discontinued.

Please see that your field men in charge of this disposal operation are instructed as to the provisions of the Order and Rules and Regulations of the Commission governing the disposal of salt water.

If the log of this well has not been filed, please comply with Paragraph 5 of the application and order.

Very truly yours,

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION

BY:

*S. S. Greider*  
S. S. Greider

SSG:su

Encls.

CC: Francis M. Raymond  
Wood River Oil & Refining Co., Inc.  
Petroleum, Inc.

PLEASE ADDRESS ALL CORRESPONDENCE TO CONSERVATION DIVISION

Sub

# PICKRELL DRILLING COMPANY

DRILLING CONTRACTORS • OIL PRODUCERS  
705 FOURTH NATIONAL BANK BLDG.  
WICHITA 2, KANSAS

## COMPLETION REPORT

### Struthers #1 Salt Water Disposal Well

Location: NE NE SW of Section 2-29S-2West - Sedgwick County, Kansas

Surface Casing 8 5/8" @ 120'

Zero 4 1/2' above Grnd.

Elevation 1364 K.B.

- 2-15-57: Moved cable tools to location; rigged up; cleaned cement from surface casing to 6'.
- 2-16-57: Drilled cement 6' to 55'
- 2-17-57: Cleaned out to 246.7'. Checked input rate @ 18 bbls. per hour (salt water). Prepared to plug back.
- 2-18-57: Plugged 246.70 to 245' w/chat, 245 to 233' w/ 1 sack calseal. No change in input. Used 1200# gravel plus 2 sx. calseal to plug back to 187'. Still same input rate.
- 2-19-57: Began cleaning out plugging material.
- 2-20-57: Cleaned out to 243', rigged up casing tools and ran 5 1/2" casing which stopped @ 87' below zero.
- 2-21-57: Pulled 5 1/2" casing and tried running it 3 times with no success. Ran 7 jts. 231' of 4 1/2" casing set @ 242' K.B. cemented to surface w/ common cement.
- 2-22-57: Cut off 8 5/8 @ 11 1/2' below K.B. 4 1/2" OD Collar @ 11' below K.B. Drilled cement 165' to 204'.
- 2-23-57: Drilled cement 204' to 244', gravel to 255'.
- 2-24-57: Cleaned out 255' to 412' P.B.T.D. Used 40 bbls. fresh water input rate 40 bbls. in 11 min. or 3.63 bbls. min or 5227 bbls. per day. Pumped 80 bbls. salt water in hole & static head @ 150'. Released cable tool rig. 4 1/2" x 2" swage on casing.

Percy L. Hall.

STRUTHER - A-1

12611  
11/26  
1952

# Well Log

Struthers #1 SWD

Surface Casing  $8\frac{5}{8}" @ 120'$  Zeroed  $4\frac{1}{2}'$  Above Crd.

Elevation 1364 K.B.

Location: NE, NE, SW of 2-29 S. 2 W. Sedgwick Co.

Soil 0 to 225 feet

Wellington 235' to 412'

Zone

Run 231' of  $4\frac{1}{2}"$  csg cemented to surface.

2-21-57

Completed: Feb, 24, 57

Commenced: Feb 15, 57

Contractor: Rickell Drilling Co.