

2 040212

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-191-21842-0000

NE | SW | NE, SEC. 18, T. 30 S., R. 2 W E

3630 feet from N/S section line

1650 feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5151

Lease Name Har El Well # 2-18

Operator: Bear Petroleum Inc

County Sumner 135.53

Name & Address 300 Sutton Place

Well Total Depth 4170 feet

Wichita, Ks. 67202

Conductor Pipe: Size \_\_\_\_\_ feet

Jim Thatcher

Surface Casing: Size 8 5/8 feet 302

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Red Tiger Drig Co. License Number 5302

Address Wichita Ks.

Company to plug at: Hour: \_\_\_\_\_ Day: \_\_\_\_\_ Month: \_\_\_\_\_ Year: 19 \_\_\_\_\_

Plugging proposal received from \_\_\_\_\_

(company name) Red Tiger Drig (phone) \_\_\_\_\_

were: 35SX 1250

35SX 360

45SX 40'

10SX RH

Plugging Proposal Received by Steve Gu  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None

Operations Completed: Hour: 1 Day: 13 Month: 7 Year: 19 85

ACTUAL PLUGGING REPORT Fill the hole with heavy mud  
run drill pipe to 1250 and spot 35 sp of  
cement. Displace with mud, pull pipe to 360 and  
spot 35 sp of cement. Pull pipe from hole, build a  
solid bridge at 40' and fill hole with 15 sacks  
of cement. Circulate 10 sacks of cement in the Rat hole.

Remarks: \_\_\_\_\_

INVOICED

DATE 9-18-85

INV. NO. 10150

WK

RECEIVED  
STATE CORPORATION COMMISSION  
SEP 18 1985  
9-18-85  
CONSERVATION DIVISION  
Wichita, Kansas

Steve Gu  
(TECHNICIAN)  
RD