

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-119-21013-00-00  
Spot: NWNWSE Sec/Twnshp/Rge: 32-32S-29W  
2200 feet from S Section Line, 2310 feet from E Section Line  
Lease/Unit Name: REXFORD Well Number: 1-32  
County: MEADE Total Vertical Depth: 6020 feet

Operator License No.: 32471  
Op Name: SUBLETTE OIL COMPANY  
Address: 924 ADELAIDE P.O. BOX 3726  
FORT SMITH, AR 72913

Conductor Pipe: Size feet:  
Surface Casing: Size 8.625 feet: 1537 WITH 725 SX CMT  
Production: Size 4.5 feet: 5910 WITH 125 SX CMT  
Liner: Size feet: 8195.65

Well Type: GAS UIC Docket No: Date/Time to Plug: 08/15/2001 1:20 PM  
Plug Co. License No.: 6547 Plug Co. Name: SARGENTS CASING PULLING SERVICE  
Proposal Rcvd. from: KIRBY LILLARD Company: SARGENTS CASING PULLING SER Phone: (316) 624-7455

Proposed Plugging Method: PUMP 25 SX CMT 200# HULLS OVER PERFS. 1ST PLUG AT 1560' WITH 50 SX CMT. 2ND PLUG AT 500' WITH 40 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: STEVE MIDDLETON Witness Type: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 08/15/2001 3:45 PM KCC Agent: STEVE MIDDLETON

Actual Plugging Report:

PBTD 5910'. PERFS AT 5679-5865'. PUMP 25 SX CMT & 200# HULLS OVER PERFS. LOAD HOLE WITH MUD. 1ST PLUG SPOT 50 SX CMT AT 1560'. 2ND PLUG PULL TO 600' & SPOT 40 SX CMT. 3RD PLUG PULL TO 40' & FILL TO SURFACE WITH 10 SX CMT. STAYED FULL.

RECEIVED  
AUG 20 2001  
KCC WICHITA

Remarks: USED COMMON CEMENT BY SARGENTS. RECOVERED 5000' OF 4 1/2" CASING.

Plugged through: CSG

District: 01

Signed   
(TECHNICIAN)

INVOICED  
DATE 8-20-01 AUG 17 2001  
INV. NO. 2002060268