

STATE OF KANSAS
STATE CORPORATION COMMISSION


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

Sumner County, Sec. 9 Twp. 30S Rge. (E) 2W(W)

Location as "NE/CNW&SW?" or footage from lines. NW/4 SE/4 SW/4
Lease Owner Messman-Rinehart Oil Company
Lease Name Love-Melia Well No. 1
Office Address 1432 Wichita Plaza, Wichita, Kansas, 67202
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed February 26 19 59
Application for plugging filed June 21 19 68
Application for plugging approved June 24 19 68
Plugging commenced July 8 19 68
Plugging completed July 10 19 68
Reason for abandonment of well or producing formation Reservoir depleted

NORTH



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production March 19 68
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Howard E. Hess, Winfield, Kansas, 67156
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3,735 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	258'	none
				5-1/2"	3735'	2627'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Set a 10' rock bridge from 3100' to 3090' and mix and dump 5 sacks of cement with dump bailer.

Set a 20' rock bridge from 200' to 240' and dump 4 cubic yards of ready mix concrete to surface.

RECEIVED
STATE CORPORATION COMMISSION
JUL 24 1968
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Flint Engineering and Construction Co.
Address Box 950, El Dorado, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
J. A. Gilliland (employee of owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. A. Gilliland
1432 Wichita Plaza, Wichita, Kansas, 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 23rd day of July, 19 68

My commission expires December 1, 1968
Barbara J. Scott Notary Public.



47

NO. 1 LOVE-MELIA

Well Record

Location: NW SE SW, Sec. 9-30S-2W
Sumner County, Kansas

Operator: Messman-Rinehart Oil Company
518 Petroleum Building
Wichita, Kansas

Contractor: Messman-Rinehart Oil Company
518 Petroleum Building
Wichita, Kansas

Casing Record: 8-5/8" @ 258' w/150 sx. cem., 4 gal, 4 c.c.
5-1/2" @ 3735' w/180 sx. cem., 3 gal.

Commenced: February 3, 1959
Completed: February 17, 1959
(rotary)
Elevation: 1328' K/B
Production: Oil

RECEIVED
STATE CORPORATION COMMISSION
JUL 24 1968
CONSERVATION DIVISION
Wichita, Kansas

--- LOG ---

Shale and Sand	90
Shale, Shells & Rock	135
Shale & Shells	258
Shale & Shells	410
Lime & Shale	1520
Shale & Lime	1720
Lime & Shale	2245
Sand & Shale	2320
Lime & Shale	2805
Lime	2845
Shale & Sand	3010
Lime & Shale	3080
Lime	3123
Lime & Shale	3658
Shale & Chert	3666 1/2 - Core #1
Chert	3671 1/2 - Core #2
Lime & Chert	3690
Lime, Chert & Shale	3725
Lime & Chert	3735 R.T.D.

Sample Tops

- 3033 - Kansas City (-1705)
- 3254 - Base Kansas City (-1926)
- 3661 - Mississippi Chert (-2333)
- 3684 - Mississippi Dolomite (-2356)

The undersigned, MESSMAN-RINEHART OIL COMPANY, hereby certifies that the above log is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.

MESSMAN-RINEHART OIL COMPANY

By: J. A. Gilliland
J. A. Gilliland

Subscribed and sworn to before me
this 27th day of March, 1959

Barbara J. Scott
Barbara J. Scott, Notary Public

My Commission Expires: December 1, 1960

COMPLETION DATA

Messman-Rinehart Oil Company
No. 1 Love-Mella
NW SE SW, Sec. 9-30S-2W
Sumner County, Kansas

- 2/25/59 - Moved in cable tools
Perf. 3062-66 w/4^S per ft. (jet)
Tested with baler - no fluid in 1½ hrs.
Perf. 3054-58 w/4^S per ft. (jet)
Ran baler and recovered 1½ gal. mdy wtr. and a teacup of oil
- 2/26/59 - Swbd. hole and treated w/500 gal. J-type acid in perms. 3054-58
Ran tubing and completed well for 25-BOPD - no water

MESSMAN-RINEHART OIL COMPANY

By:


Roger L. Messman, Partner

RECEIVED
STATE CORPORATION COMMISSION
JUL 24 1968
CONSERVATION DIVISION
Wichita, Kansas