

OR

FORMATION PLUGGING RECORD

Strike out upper line when reporting plugging of formations.

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division,
State Corporation Commission,
800 Bittling Building,
Wichita, Kansas.

NORTH

Locate well correctly on above
640 A. Plat

Sumner County, Sec. 9 Twp. 30S Rge 2W (E) (W)
Lease Name Lotter B WELL NO. 1
Lease Owner Champion Refining Company
Office Address 1514, Oklahoma
Character of Well (Oil, Gas or Dry) Oil Total Depth of Well 3255 Feet
Date, well, completed August 31st 1935
Application for plugging and log of well filed September 4th 1935
Application for plugging approved September 5th 1935
Plugging Commenced September 5th 1935
Plugging Completed September 23rd 1935
Reason for abandonment of well or producing formation Not paying at 3056ft. Dry below 3056ft.
If a producing well is abandoned, date of last production May 5th 1935
Was permission obtained from the Conservation Division or its agents before plugging was commenced? From Conservation Division
Name of Conservation Officer who supervised plugging of this well W. G. Buffington
Producing formation Lime K.C. Depth to top 3042' Bottom 3056'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Gray lime	water	261	70'	1 1/2"	261' 1"	261' 1"
" sandy	water	500	805	12 1/2"	1088	1088
" lime	water	974	1024	10"	2002' 9"	1921 "
Lime sandy	Gas	1905'	1910	8"	2045' 13"	2045' 13"
Water Sand	water	1915	1917	6-5/8"	3182	3182
Gray sand	Gas	2030	2030			
" "	water	2030	2055			
Sand	water	2250	2250			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Sand	water	2500	2575
Sand	Gas	2750	2835
Sand	Oil	3042	3056
Lime	Oil & water	3157	3161
Lime sandy	water	3177	3182
Lime	Oil & water	3182	3203
Lime	water	3203	3220

PLUGGING
FILE SEC-9-30-R-21
BOOK PAGE 17 LINE 20

Hole mudded with steam jet. Started a 6-5/8" casing and mudded. Mudded hole as was pulled 6 casing. We removed the boys and then with each string of casing thereby filling the hole from top to bottom with heavy mud from fluid. Hauled mud with truck and filled hole solid from 70 feet to collar.

(If additional description is necessary use BACK of this sheet)

Does the above conform strictly to the Conservation Division regulations? Yes
Was exception made? No If so describe _____
Correspondence regarding this well should be addressed to Champion Refining Company
Address 1514, Oklahoma

STATE OF Kansas, COUNTY OF Sedgewick, ss.

Geo. V. Wentworth (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Geo. V. Wentworth
Clearwater, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 24 day of Sept, 1935


My Commission Expires Sept. 25, 1935
My commission expires _____
W. G. Buffington Notary Public.

15-191-10197-0001
D + a owned

DISTRICT CONSERVATION AGENT'S REPORT

To

State Corporation Commission,
Conservation Division,
800 Bitting Building,
Wichita, Kansas.



File No. 17-20

Location ? ne 1/4

Sec. 9 Twp. 30 Rge. 2W


I have today completed supervision of plugging of

Well No. 1 Lease Latta B

Operator Chaplin.

Field Latta County Sumner

Total Depth 3056 Feet.



(Describe briefly the manner in which well was plugged)

Filled with good heavy mud and a plug was set at each casing point filled
at top with good dirt.

W. G. Beffington
District Conservation Agent
Date _____