

STATE OF KANSAS
STATE CORPORATION COMMISSION


Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

Meade County. Sec. 15 Twp. 32S Rge. (#)30 (W)
Location as "NE/CNW/SW" or footage from lines C NE SW
Lease Owner A. L. Abercrombie, Inc.
Lease Name B. H. Smith Well No. 1
Office Address 801 Union Center, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Gas-Oil
Date well completed May 27, 19 61
Application for plugging filed Nov. 13, 19 67
Application for plugging approved Nov. 16, 19 67
Plugging commenced Nov. 24, 19 67
Plugging completed Nov. 27, 19 67
Reason for abandonment of well or producing formation Non-Commercial

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production Nov. 8, 19 67
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. E. Eves, Sublette, Kansas
Producing formation Morrow Depth to top 5629' Bottom 5644' Total Depth of Well 5798 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	1576'	None
				5-1/2"	5800'	2704'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Rig up pump truck to plug off perforations @5630'. Stop plug @5530'.
Used 20 sx. cmt. and 1 sx. hulls. Mixed 35 sx. cmt. @ 700' - 600'.
Put 15 sx. cmt. @ 45' to 0'.

RECEIVED
STATE CORPORATION COMMISSION
DEC 14 1967
12-11-67
CONSERVATION DIVISION
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sargents Casing Pulling Service
Address P. O. Box 506; Liberal, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
A. L. Abercrombie (employer or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]
801 Union Center; Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 8th day of December, 19 67

My commission expires March 31, 1970

Margy Dee Montgomery
Margy Dee Montgomery Notary Public.

LEASE: B. H. SMITH #1
OPERATOR: MUSGROVE DRILLING CO.
CONTRACTOR: EARL F. WAKEFIELD
CON: 4-14-61 COMP: 5-8-61

LOCATION: C NE SW
SECTION 15-32S-30W
MEADE COUNTY, KANSAS
CASING: 8 5/8" Set at 1575.75'
5 1/2" Set at 5798'

Surface clay and sand	397
Clay, Gyp, Red Bed	864
Red Bed and Sand	1250
Red Bed, Anhydrite and Shale	1515
Red Shale	1565
Anhydrite	1585
Shale and Red Bed	2065
Red Bed and Shale	2265
Shale with streaks Anhydrite	2476
Lime and Shale	2632
Lime and Shale, Anhydrite	2687
Lime	2838
Lime and Shale	3257
Chalk	3300
Lime and chalk streaks	3492
Lime and Shale	3438
Shale and Lime	3731
Shale, streaks Lime	3776
Lime	3845
Lime and Shale	3990
Lime	4008
Lime and chalk	4090
Lime	4202
Lime and Chalk	4270
Shale and chalky Lime	4350
Lime and Shale	4564
Lime	4602
Lime and Shale	4802
Shale and Lime	4870
Lime	4956
Lime and Shale	5181
Lime	5293
Lime and Shale	5346
Lime	5570
Lime and Shale	5648
Lime	5672
Lime and Shale	5743
Lime	5802
T. D.	5802

STATE OF KANSAS RECEIVED
CONSERVATION DIVISION
Wichita, Kansas
APR 29 1968
FOREIGN SUBMISSION

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

I hereby certify that the above is a true and correct copy of the log on the B. H. SMITH #1 well, located C NE SW, SECTION 15-32S-30W, MEADE COUNTY, KANSAS.

EARL F. WAKEFIELD
By Earl F. Wakefield

Subscribed and sworn before me this 22nd day of May, 1961

Wanda W. Riley
WANDA W. RILEY NOTARY

My commission expires January 25, 1965