

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Meade County, Sec. 14 Twp. 32S Rge. 30W E/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines
1320' FNL & 1320' FWL


Lease Owner American Petrofina Co. of Texas
Lease Name RICHARDSON Well No. 1
Office Address 4613 Jacksboro Hwy, Wichita Falls, TX
Character of Well (Completed as Oil, Gas or Dry Hole) 76302
Dry Hole

Date Well completed October 23, 1980
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced October 23, 1980
Plugging completed October 23, 1980
Reason for abandonment of well or producing formation

Dry Hole
If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Bill Owen of Pratt, KS
Producing formation Depth to top Bottom Total Depth of Well 6100'
Show depth and thickness of all water, oil and gas formations.



Locate well correctly on above Section Plot

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	Surface					
	Casing	0	1622'	8-5/8"	1622'	NONE

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plugged Hole w/50 sax cement @ 1600',
40 sax cement @ 719', 10 sax cement @
-3' to 33'. Job Completed @ 3 A.M.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Halliburton

RECEIVED
STATE CORPORATION COMMISSION
NOV 7 1980

STATE OF KANSAS COUNTY OF SEDGWICK
John R. Bartholomew of Sage Drilling


being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) John R. Bartholomew
222 Sutton Place, Wichita, KS 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 28th day of October, 1980

Louise K. Whitted
Notary Public.

My commission expires



DRILLERS LOG

RICHARDSON NO. 1

CASING RECORD:	OPERATOR: American Petrofina of TX.	DESCRIPTION:
8-5/8" set @ 1622' w/800 sax cement	CONTRACTOR: Sage Drilling Co., Inc.	1320' FNL & 1320' FWL
TOTAL DEPTH: 6100'	COMMENCED: October 9, 1980	Sec. 14-32S-30W Meade County, Kansas
	COMPLETED: October 23, 1980	

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Sand & Red Bed	0	650	
Red Bed	650	1274	
Sand & Red Bed	1274	1628	
Red Bed & Lime	1628	1768	
Red Bed & Anhydrite	1768	2235	
Shale	2235	2595	
Lime & Shale	2595	3800	
Shale & Lime	3800	3886	
Lime & Shale	3886	4605	
Shale & Lime	4605	4810	
Lime & Shale	4810	5119	
Shale & Lime	5119	5250	
Lime & Shale	5250	6100	Logged Hole, Ran DST #1, DST #2, DST #3, D & A

I certify that this is a true and correct copy of the log on the (above captioned well to the best of my knowledge.

RECORDED & INDEXED
 NOV 7 1980
 SAGE DRILLING CO., INC.
 By John R. Bartholomew
 John R. Bartholomew, Kansas

Subscribed and sworn to before me this 27th day of October, 1980.

Louise K. Whitted
 Louise K. Whitted, Notary Public

LOUISE K. WHITTED
 STATE NOTARY PUBLIC
 Sedgwick County, Kansas
 My Appt. Expires 11-26-82