

15-119-00060-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Meade County, Sec. 8 Twp. 32 Rge. (E) 30 (W)

Location as "NE/CNW/SW" or footage from lines C NW SW
Lease Owner Earl F. Wakefield
Lease Name Langhofer Well No. 1
Office Address 515 Union Center Bldg., Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed November 15 1956
Application for plugging filed August 8 1957
Application for plugging approved _____ 19____
Plugging commenced August 8 1957
Plugging completed August 9 1957
Reason for abandonment of well or producing formation Dry Hole

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 5716 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				5 1/2"	5695	2808
				8 5/8"	1600	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with mud to 5545'
Dumped 5 sks cement with dump bailer,
pulled pipe, pumped 35 sks Jel mud and
50 sks cement, pumped down 500' with
Jel mud and cap top of hole with 10sks cement

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Earl F. Wakefield
Address 515 Union Center Bldg., Wichita, Kansas

STATE OF KANSAS COUNTY OF SEDGWICK, ss.
Earl F. Wakefield (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Earl F. Wakefield
515 Union Center Bldg., Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 15 day of August, 19 57

My commission expires July 26, 1958 C. A. Snow Notary Public.

PLUGGING
FILE SEC 8 T. 32 R. 3aw
BOOK PAGE 37 LINE 24

8-16-57
KOS 10...
CONSERVATION DIVISION

LEASE: Langhofer #1
OWNER: Earl F. Wakefield
CONTRACTOR: Earl F. Wakefield
COMM: 10-13-56 COMP: 11-15-56

LOCATION: C NW SW 8-32-30W
Meade County, Kansas
CASING: 8 5/8" Set @ 1600'
5 1/2" Set @ 5695' K.B.

Elevation: 2780 D.F. 2770 G.L.

Sand & Clay	230	Lime	4901
Sand	415	Lime & Shale	4942
Red Bed & Gyp	580	Shale W/Stks Lime	5027
Red Bed, Gyp & Shells	790	Lime & Shale	5118
Red Bed W/Stks Anhydrite	1010	Lime	5238
Lime	1080	Lime & Stks Shale	5282
Red Bed & Shale	1262	Lime	5303
Anhydrite & Red Bed	1454	Lime & Shale	5556
Anhydrite, Red Bed, Stks Lime	1600	Sand (Morrow)	5561
Red Bed	1630	Shale	5568
Salt	1650	Lime	5588
Anhydrite	1760	Sand & Lime	5650
Red Bed & Chert	2000	Lime & Shale	5716
Red Bed, Shale & Lime	2182	T.R.D.	5716
Lime & Shale	2529		
Lime & Chert Stgs	2576		
Lime & Chert	2618		
Lime	2755		
Shale	2774		
Lime & Shale	3214		
Lime	3295		
Lime & Chalk	3512		
Chalky Lime & Shale	3704		
Lime & Shale	3996		
Black Gray Lime	4100		
Lime	4133		
Lime & Shale	4475		
Lime	4565		
Lime & Shale	4624		
Lime	4687		
Lime, Shale, Stks Chert	4725		
Lime	4767		
Lime & Shale	4803		

STATE OF KANSAS)
) SS:
COUNTY OF SEDGWICK)

I hereby certify that the above is a true and correct copy of the log of the Langhofer #1 well located C NW SW 8-32-30W, Meade County, Kansas

Earl F. Wakefield

Subscribed and sworn to before me this 23rd day of November 1956

[Signature]

My Commission Expires: 7-26-58

RECEIVED
STATE CORPORATE COMMISSION

AUG 16 1957

COMMISSION DIVISION
Meade County, Kansas

PLUGGING
FILE SEC 8 T. 32 R. 30W
BOOK PAGE 37 LINE 24