

STATE OF KANSAS  
 STATE CORPORATION COMMISSION  
 200 Colorado Derby Building  
 Wichita, Kansas 67202

WELL PLUGGING RECORD  
 K.A.R.-82-3-117

15-119-20076-0000

API NUMBER n/a

LEASE NAME Roberts A

WELL NUMBER 1

4290 Ft. from S Section Line

990 Ft. from E Section Line

SEC. 29 TWP. 32S RGE. 29 (N) or (W)

COUNTY Meade

Date Well Completed 1971

Plugging Commenced 10/4/82

Plugging Completed 10/7/82

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

LEASE OPERATOR Kaiser-Francis Oil Company

ADDRESS P. O. Box 21468, Tulsa, OK 74121-1468

PHONE#(918) 491-4314 OPERATORS LICENSE NO. 6568

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on n/a (date)

by Steve Durant (KCC District Agent's Name).

Is ACO-1 filed? on old form If not, Is well log attached? -

Producing Formation Marmaton Depth to Top 4784 Bottom 5224 T.D. 5320

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
<u>Marmaton</u>	<u>Oil</u>	<u>4784</u>	<u>5224</u>	<u>8 5/8</u>	<u>1448</u>	<u>-0-</u>
				<u>4 1/2</u>	<u>5320</u>	<u>2000</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from    feet to    feet each set. Set CIBP @ 4737' w/1 sx cmt on top. Set cmt retainer @ 2020' & sqz'd w/400 sxs cmt.

Pumped 25 sxs cmt from 1448' to 1348'. Pumped 25 sxs cmt from 750' to 650'. Pumped 10 sxs cmt from 40' to surface. Cut off & capped 8 5/8" casing 3' below ground level.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sargent's Casing Pulling Service License No. 6547

Address Box 506, Liberal, KS 67901 RECEIVED  
STATE CORPORATION COMMISSION

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Kaiser-Francis Oil Company SEP 13 1994

STATE OF Oklahoma COUNTY OF Tulsa, ss.

Charlotte Van Valkenburg

(Employee of Operator) WICH (Operator) IN

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) C. Jan Valkenburg

(Address) P. O. Box 21468, Tulsa, OK 74121-1468

SUBSCRIBED AND SWORN TO before me this 9th day of September, 1994

And Imhoff  
 Notary Public

My Commission Expires: 12-23-97