

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
200 Colorado Derby Building  
Wichita, Kansas 67202

FORM CP-1  
Rev. 6/4/84

WELL PLUGGING APPLICATION FORM  
(File One Copy)

API NUMBER 15-175-21,019-0000 (of this well)  
(This must be listed; if no API# was issued, please note drilling completion date.)

LEASE OPERATOR Shepler & Thomas, Inc. OPERATORS LICENSE NO. 3711

ADDRESS P.O. Box 2164, Evergreen, Colorado 80439 PHONE # (303) 674-3503

LEASE (FARM) Kulp WELL NO. #1-33 WELL LOCATION SW-SE COUNTY Seward

SEC. 33 TWP. 32S RGE. 31 (E) or (W) TOTAL DEPTH 6000 PLUG BACK TD 5988

Check One:

OIL WELL  GAS WELL  D & A  SWD or INJ WELL  DOCKET NO. \_\_\_\_\_

SURFACE CASING SIZE 8 5/8 SET AT 1599 CEMENTED WITH 457 SACKS

CASING SIZE 4 1/2 SET AT 6000 CEMENTED WITH 350 SACKS

PERFORATED AT St. Louis 5923-26; 5941-51

CONDITION OF WELL: GOOD  POOR  CASING LEAK  JUNK IN HOLE

OPERATOR'S SUGGESTED METHOD OF PLUGGING THIS WELL Pump 2 sx cottonseed hulls and 50 sx  
Class H to perforations @ 5923-26; 5941-51; mud to 1650; 50 sx from 1650 to  
1550; 35 sx @ 620-550; 35 sx from 40' to 0'

(If additional space is needed use back of form)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? NO IS ACO-1 FILED? YES  
(If not, explain) filed with ACO-1

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN January 12, 1990 @ 8:00 AM

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et seq AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

R. F. Burke

PHONE # (316) 624-0750

ADDRESS P.O. Box 1162, Liberal, Kansas 67905-1162

STATE CORPORATION COMMISSION  
1-2-90  
JAN 2 1990 6/90

PLUGGING CONTRACTOR Sargent's Casing Pullers

LICENSE NO. 6547

ADDRESS Liberal, Kansas 67901

PHONE # (316) 624-7455  
CONSERVATION DIVISION  
Wichita, Kansas

PAYMENT WILL BE GUARANTEED BY OPERATOR OR AGENT

SIGNED: RFB

AGENT (Operator or Agent)

DATE: December 28, 1989

①



Kansas Corporation Commission

MIKE HAYDEN  
KEITH R. HENLEY  
RICH KOWALEWSKI  
MARGALEE WRIGHT  
JUDITH MCCONNELL  
FRANK A. CARO, JR.

GOVERNOR  
CHAIRMAN  
COMMISSIONER  
COMMISSIONER  
EXECUTIVE DIRECTOR  
GENERAL COUNSEL

THIS NOTICE  
APR 02 1990  
EXPIRES

CONSERVATION DIVISION  
SHARI FEIST ALBRECHT, DIRECTOR  
200 Colorado Derby Bldg.  
202 W. 1st Street  
Wichita, KS 67202-1286  
(316) 263-3238

January 2, 1990  
NOTICE OF RECEIPT OF  
WELL PLUGGING APPLICATION

Shepler & Thomas, Inc.  
P.O. Box 2164  
Evergreen, CO 80439

Kulp #1-33  
SW SE  
SEc. 33-32-31W  
Seward County

Gentlemen:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging. Please contact the district office to review your proposed plugging method at least five (5) days before plugging the well.

It has recently come to my attention that the form CP-1 has been filed by operators other than the owner or operator of the well and without the consent of the owner or operator. The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well. The CP-1 is simply reviewed to determine compliance with plugging rules and regulations.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,

*Shari Feist Albrecht*

Shari Feist Albrecht  
Director

District: #1 304 W. McArtor  
Dodge City, KS 67801  
(316) 225-6760