

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 6/4/84

WELL PLUGGING APPLICATION FORM
(File One Copy)

API NUMBER 15-175-21,072-0000 (of this well)
(This must be listed; if no API# was issued, please note drilling completion date.)

LEASE OPERATOR Shepler & Thomas, Inc. OPERATORS LICENSE NO. 3711 ^{3/80}
ADDRESS P.O. Box 2164, Evergreen, Colorado 80439 PHONE # (303) 674-3503
LEASE (FARM) Stoll WELL NO. #3-30 WELL LOCATION C-NE-NE COUNTY Seward
SEC. 30 TWP. 32S RGE. 31 (E) or (W) TOTAL DEPTH 5765 PLUG BACK TD 5731

Check One:

OIL WELL GAS WELL D & A X SWD or INJ WELL DOCKET NO.
SURFACE CASING SIZE 8 5/8 SET AT 1648 CEMENTED WITH 475 SACKS
CASING SIZE 4 1/2 SET AT 5764 CEMENTED WITH 50 SACKS
PERFORATED AT Chester 5688-92; Marmaton 5083-85; 5002-14

CONDITION OF WELL: GOOD X POOR CASING LEAK JUNK IN HOLE

OPERATOR'S SUGGESTED METHOD OF PLUGGING THIS WELL Set CIBP @ 5650 with 2 sx cement on
and 50 sx Class H
top. Pump 2 sx cottonseed hulls to perforations @ 5083-85 and 5002-14, mud
to 1700, 50 sx @ 1700-1600, 35 sx @ 620-550; 35 sx @ 40' to 0'
(If additional space is needed use back of form)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? NO IS ACO-1 FILED? YES
(If not, explain) Filed with ACO-1

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN January 17, 1990 @ 8:00 AM

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et seq AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS: 1-2-90
R. F. Burke PHONE # (316) 624-0750

ADDRESS P.O. Box 1162, Liberal, Kansas 67905-1162 ^{RECEIVED}
STATE CORPORATION COMMISSION

PLUGGING CONTRACTOR Sargent's Casing Pullers LICENSE NO. 6547 ^{6/90}

ADDRESS Liberal, Kansas 67901 PHONE # (316) 624-7455 ^{CONSERVATION DIVISION}
Wichita, Kansas

PAYMENT WILL BE GUARANTEED BY OPERATOR OR AGENT SIGNED: RFB
AGENT (Operator or Agent)

DATE: December 28, 1989

State of Kansas



Kansas Corporation Commission

MIKE HAYDEN
KEITH R. HENLEY
RICH KOWALEWSKI
MARGALEE WRIGHT
JUDITH MCCONNELL
FRANK A. CARO, JR.

GOVERNOR
CHAIRMAN
COMMISSIONER
COMMISSIONER
EXECUTIVE DIRECTOR
GENERAL COUNSEL

THIS NOTICE

APR 02 1990

EXPIRES

CONSERVATION DIVISION
SHARI FEIST ALBRECHT, DIRECTOR
200 Colorado Derby Bldg.
202 W. 1st Street
Wichita, KS 67202-1286
(316) 263-3235

January 2, 1990
NOTICE OF RECEIPT OF
WELL PLUGGING APPLICATION

Shepler & Thomas, Inc.
P.O. Box 2164
Evergreen, CO 80439

Stoll #3-30
Sec. 30-32-31W
C NE NE
Seward County

Gentlemen:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging. Please contact the district office to review your proposed plugging method at least five (5) days before plugging the well.

It has recently come to my attention that the form CP-1 has been filed by operators other than the owner or operator of the well and without the consent of the owner or operator. The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well. The CP-1 is simply reviewed to determine compliance with plugging rules and regulations.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,

Shari Feist Albrecht
Shari Feist Albrecht
Director

District: #1 304 W. McArtor

Dodge City, KS 67801

(316) 225-6760