


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Seward County, Sec. 25 Twp. 32S Rge. (E)31 (W)
Location as "NE/CNWxSWx" or footage from lines 150' N C SE NE
Lease Owner Tilco et al
Lease Name Stewart Well No. 2
Office Address P.O. Box 486 Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) dry hole
Date well completed November 17 1969
Application for plugging filed November 17 1969
Application for plugging approved November 17 1969
Plugging commenced November 17 1969
Plugging completed November 17 1969
Reason for abandonment of well or producing formation dry hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Edgar Eaves
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well _____ Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	1560'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Bottom Plug 900'-1000' with 35 sacks cement.
Top Plug @ 45' to bottom of cellar with 15 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION
DEC 12 1969
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Leben Drilling, Inc.
Address P.O. Box 486 Great Bend, Kansas

STATE OF KANSAS, COUNTY OF BARTON, ss.
James R. Rodgers (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) James R. Rodgers James R. Rodgers
P.O. Box 486 Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 10th day of December, 1969

My commission expires November 13, 1973
Helen L. Lindenmuth Notary Public.

RECEIVED
STATE CORPORATION COMMISSION
DEC 12 1969
CONSERVATION DIVISION
Wichita, Kansas


DRILLER'S LOG

COMPANY: Tilco et al
CONTRACTOR: LEBEN DRILLING, INC.
FARM: STEWART #2
LOCATION: 150' N C SE NE SECTION 25-32S-31W
SEWARD COUNTY, KANSAS
COMMENCED: 11-6-69
COMPLETED: 11-17-69

0	440	Surface Soil & Sand
440	1140	Surface
1140	1549	Red Bed
1549	1560	Anhydrite
1560	1640	Anhydrite & Red Bed
1640	2095	Shell & Shale
2095	4328	Shale & Lime
4328	4985	Lime
	<u>4985</u>	<u>RTD D & A</u>

8 5/8" 24# New Surface Casing set @ 1560' with 600 sacks 50/50 Pozmix with 6% Gel and 2% C.C. followed with 225 sacks Common 2% C.C.

I, James R. Rodgers, do hereby certify that the above and foregoing is a true and correct copy of the log of the Stewart #2 Well, located 150' N C SE NE of Section 25, Township 32 South, Range 31 West, Seward County, Kansas, as reflected by the records of Leben Drilling, Inc.


James R. Rodgers

STATE OF KANSAS)
) SS
COUNTY OF BARTON)

Subscribed and sworn to and before me, a Notary Public, in and for Barton County, Kansas, this 10th day of December, 1969.


Helen L. Lindenmuth

My Commission Expires:
November 13, 1973