

API NUMBER 15-175-20,100-0000
 LEASE NAME Manka
 WELL NUMBER 1
4770 Ft. from S/NE Line of Section (circle one)
4620 Ft. from E/NE Line of Section (circle one)

TYPE OR PRINT
 NOTICE: Fill out completely and return
 to Cons. Div. office within 30 days.

LEASE OPERATOR Kaiser-Francis Oil Company
 ADDRESS P. O. Box 21468
 CITY, STATE, ZIP Tulsa, OK 74121-1468
 PHONE#(918) 491-4314 OPERATORS LICENSE NO. 6568
 Character of Well Gas
 (Oil, Gas, D&A, SWD, Input, Water Supply Well)

SPOT LOCATION - N/2 - NW - NW
 SEC. 25 TWP. 32 S. RGE 31 (#) or (W)
 COUNTY Seward
 Date Well Completed 7/15/86
 Date Plugging Commenced 2/12/98
 Date Plugging Completed 2/13/98

The plugging proposal was approved on 2/11/98 (date)
 by Gary Winters (KCC District Agent's Name)

Is ACO-1 filed? Yes If not, is well log attached? -

Producing Formation(s) Council Grove Depth to Top 3070 Bottom 3177 T.D. 6130

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULL OUT
Council Grove	Gas	3070	3177	8 5/8	1580	-0-
				5 1/2	4473	2231
				4 1/2 lnr	4080-6130	-0-

Described in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set.

Mixed 25 sxs cmt + 2 sxs hulls from 3070' - 2870'. Located free-point on 5 1/2" csg & shot off @ 2231'. Mixed 50 sx cmt plug from 1610' - 1460' @ bottom of 8 5/8" casing. Mixed 40 sx cmt plug from 650' - 550'. Mixed 10 sx cmt plug from 40' to surf. Cut off & capped 8 5/8" csg 4' below ground level. Used mud between all plugs.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sargent & Horton Plugging, Inc.
 License No. 31151
 Address Rt. 1 Box 49BA, Tyrone, OK 73951-9731
 NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Kaiser-Francis Oil Company
 STATE OF Oklahoma COUNTY OF Tulsa, ss.

RECEIVED
 KANSAS CORP COM
 1998 MAR 30

Charlotte Van Valkenburg (Employee of Operator or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) C. Jan Valkenburg
 (Address) P. O. Box 21468, Tulsa, OK 74121-1468

SUBSCRIBED AND SWORN TO before me this 27th day of March, 19 98

My Commission Expires: 10-4-99 Notary Public