

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-17520412-A-000/

LEASE NAME FIESER

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 1-23

4950 Ft. from S Section Line

1175 Ft. from E Section Line

LEASE OPERATOR LEE BANKS OIL CO.

SEC. 23 TWP. 32S RGE. 31W (E) or (W)

ADDRESS 200 WEST DOUGLAS STE. 550 WICHITA, KS 67202

COUNTY SEWARD

PHONE# (316) 267-0783 OPERATORS LICENSE NO. 5152

Date Well Completed not completed

Character of Well OIL - non commercial

Plugging Commenced 2-19-90

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 2-26-90

The plugging proposal was approved on NOVEMBER 17, 1989 (date)

by MR. MIKE SPAIN (KCC District Agent's Name).

Is ACO-1 filed? YES If not, Is well log attached? _____

Producing Formation Marmaton/Non. Prod. Depth to Top 5061 Bottom 5066 T.D. 5150

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	1575	-0-
Marmaton	Non productive	5061	5066	4 1/2	5148	3516

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each set.
2-19-90 Pumped 25sx class H cement between rubber plugs displaced to 4800' to 5080' with 76 bbls 9.5# 40 vis. mud. Pumped down casing tagged by wireline. 2-26-90 Pumped 50sx class H cement 1605' to 1505', circulation method with 24 bbls 9.5# 40 vis. mud. 2-26-90 Pumped 40sx class H cement 760' to 660', circulation method with 10 bbls 9.5# 40 vis. mud. 2-26-90 Pumped 10sx class H cement 4'-44' same method. If additional description is necessary, use back of this form.

Name of Plugging Contractor JERRY DUNKIN, INC. License No. 8733

Address P.O. BOX 389 ENID, OKLAHOMA 73702

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Lee Banks, d/b/a Banks Oil Company

STATE OF Kansas COUNTY OF Sedgwick, ss.

Lee Banks

(Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

RECEIVED
STATE CORPORATION COMMISSION

(Signature) [Signature]

(Address) 200 W. Douglas, Suite 550, Wichita, Ks

MAR 23 1990

SUBSCRIBED AND SWORN TO before me this 22nd day of March, 1990
CONSERVATION DIVISION
Wichita, Kansas

[Signature]
Notary Public

My Commission Expires MAY
Notary Public - State of Kansas
My Appt. Expires

Aug. 28, 1992