

STATE OF KANSAS
STATE CORPORATION COMMISSION
Finney State Office Building
30 South Market, Rm 2078
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-175-20332-00-01

LEASE NAME GANO

WELL NUMBER A-7

RECEIVED

OCT 28 2002

KCC WICHITA

NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days

664 Ft. from S Section Line

4285 Ft. from E Section Line

SEC. 35 TWP. 32S RGE 31 (E) or (W)

COUNTY SEWARD

Date Well Completed 11-9-1977

Plugging Commenced 9-11-2002

Plugging Completed 9-11-2002

LEASE OPERATOR ANADARKO PETROLEUM CORPORATION

ADDRESS 701 S TAYLOR, STE 400 AMARILLO, TX 79101

PHONE # (806) 457-4600 OPERATORS LICENSE NO. 4549

Character of Well GAS

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 9-5-2002 (date)

by RICHARD LACEY (KCC District Agent's Name).

Is AC0-1 filed? YES If not, is well log attached? _____

Producing Formation CHASE Depth to Top 2578 Bottom 2632 T.D. 3220

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
CHASE	GAS	2578	2632	8-5/8"	5222	0
				4-12"	3219	0

Describe in detail, the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each set. PMP 2 SXS HULLS AND 15 SXS CMT FROM 2578-2378. PMP 20 SXS CMT FROM 1700-1500. PMP 40 SXS CMT FROM 500 TO SURFACE. CUT OFF AND CAP 4-1/2" AND 8-5/8" CSG 3' BELOW SURFACE. RDMO AND RESTORE LOCATION.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor SARGENT AND HORTON PLUGGING, INC. License No. 31151

Address RT 1 BOX 498A, TYRONE, OK 73951-9731 PHONE: (580) 854-6515

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: ANADARKO PETROLEUM CORPORATION

STATE OF TEXAS COUNTY OF POTTER, ss.
CRAIG R. WALTERS, P.E., DIVISION PRODUCTION ENGINEER (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Craig R. Walters
CRAIG R. WALTERS, P.E., DIV. PROD. ENGINEER

(Address) 701 S. TAYLOR, STE 400 AMARILLO, TX 79101



SWORN TO before me this 25 day of October, 2002

Lori Pearson
Notary Public

My Commission Expires: 2/28/03

OR