

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

Seward County, Sec. 34 Twp. 32S Rge. (E) 31 (W)

Location as "NE/CNW/SW" or footage from lines C NE SW

Lease Owner Anadarko Production Company

Lease Name Singley Well No. 1

Office Address Box 351 Liberal, Kansas 67901

Character of Well (completed as Oil, Gas or Dry Hole) Gas

Date well completed Oct. 23 19 62

Application for plugging filed Feb. 9 19 70

Application for plugging approved Feb. 11 19 70


Plugging commenced March 13 19 70

Plugging completed March 13 19 70

Reason for abandonment of well or producing formation Well no longer economical to produce,

If a producing well is abandoned, date of last production January 19 70

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Mr. Ed Eves Box "F" Sublette, Kansas 67877

Producing formation Morrow Depth to top 5515 Bottom 5581 Total Depth of Well 6085 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Morrow	Gas	5515	5581	8 5/8"	2299'	None
				4 1/2"	6083'	3606'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Mixed 20 sacks cement and pumped plug to 4800'.
Spotted 35 sacks cement from 600 to 500'.
Spotted 15 sacks cement from 45' to surface.
Hole filled with mud between each plug.

RECEIVED
STATE CORPORATION COMMISSION
MAR 23 1970
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Sargent's Casing Pulling Service, Box 506, Liberal, Kansas 67901
Address Liberal, Kansas 67901

STATE OF Kansas, COUNTY OF Seward, ss.
K. Downey (employee of owner) or (owner or operator) of the above-described

well being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]

Box 351, Liberal, Kansas 67901
(Address)

DESCRIBED AND SWORN TO before me this 19th day of March, 19 70



My Commission Expires April 28, 1971

[Signature]

Notary Public.

My commission expires _____


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- WHITEHALL OIL COMPANY
Farm- Singley No. 1

SEC. 94 T. 32 R. 31W
C NE SW

Total Depth. 6085'
Comm. 10-16-62 Comp. 11-8-62
Shot or Treated.
Contractor. P S & B Drilling
Issued. 2-16-63

County Seward
KANSAS



Elevation. 2779' DE

Production. 775,000 CFG/PD & 6 BOPD.

CASING:

8 5/8" 2309' cem w/650 sk.
4 1/2" 6085' cem w/350 sk.

Figures indicate Bottom of Formations.

sand & clay	500
red bed & shells	1037
shale	1050
sand	1225
shale & lime	1545
lime	2309
lime & shale	2974
lime	3287
chalky lime & shale	3541
lime & shale	4538
lime	4879
lime & shale	4927
lime	5298
lime & shale	5529
lime & shale w/sand	5637
lime & shale	5742
lime	6085
Total Depth	

TOPS: SCOUT	
Council Grove	2993
Toronto	4299
Lansing	4408
Marmaton	5038
Morrow	5526
Morrow Sand	5555
Morrow Sand	5571
Chester	5602
St. Genevieve	5782
St. Louis	5898

RECEIVED
STATE CORPORATION COMMISSION
MAY 13 1970
CONSERVATION DIVISION
Wichita, Kansas