


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Comm.  
245 North Water  
Wichita, KS 67202

Seward County, Sec. 30 Twp. 32S Rge. 31W E/W  
Location as "NE/CNW SW  $\frac{1}{4}$ " or footage from lines \_\_\_\_\_  
C SW SW  $\frac{1}{4}$   
Lease Owner Rupe Oil Co. Inc.  
Lease Name Reiss Well No. 1  
Office Address Box 2273 - 434 Ohio Wichita, Kansas 67201  
Character of Well (Completed as Oil, Gas or Dry Hole) \_\_\_\_\_



Locate well correctly on above  
Section Plot

Date Well completed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging filed 4-13 1979  
Application for plugging approved 4-15 1979  
Plugging commenced 4-19 1979  
Plugging completed 4-20 1979  
Reason for abandonment of well or producing formation \_\_\_\_\_

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Clarence Thomas  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well \_\_\_\_\_  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	1408	none
				2 3/8	5459	2600

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Pump 20 sks. of cement & 2 sks. of hulls from 5562 to 5300  
Pump 35 sks. of cement from 1400 to 1300  
Put 10 sks. of cement from 40 to 0

RECEIVED  
STATE CORPORATION COMMISSION

MAY 18 1979

CONSERVATION DIVISION  
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sargent's Casing Pulling Ser. Box 506 Liberal, Kansas 67901 Ks.No 511

STATE OF Kansas COUNTY OF Seward, ss.  
(employee of owner) or (owner or operator)  
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Robert Sargent  
620 So. Lincoln Liberal, Kansas 67901  
(Address)

SUBSCRIBED AND SWORN TO before me this 16th day of May, 1979

Dorothy Sargent  
Notary Public.

My commission expires Dec. 11th. 1981

STATE NOTARY PUBLIC  
DOROTHY SARGENT  
Seward County, Kansas  
My Appt Exp. Dec. 11, 1981

DRILLERS LOG

REISS NO. 1

CASING RECORD:	OPERATOR: Glen N. Rupe	DESCRIPTION:
8-5/8" @ 1409'	CONTRACTOR: Sage Drilling Co.	C SW SW
w/730 sax cement	COMMENCED: April 4, 1974	Sec. 30-32S-31W
TOTAL DEPTH:	COMPLETED: April 21, 1974	Seward Co., Kansas
5998'		ELEVATION: 2790KB

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Surface Sand & Clay	0	375	
Chert & Red Bed	375	935	
Red Bed & Sand	935	1409	
Shale & Anhydrite	1409	2106	
Shale & Lime	2106	2473	
Lime & Shale	2473	3089	
Lime, Shale & Dolomite	3089	3268	
Lime & Shale	3268	5391	
Shale & Lime	5391	5471	
Lime & Shale	5471	5662	
Lime	5662	5737	
Lime & Shale	5737	5974	
Lime	5974	5998	4 1/2" set @ 5664' w/150 sax Pozmix


RECEIVED  
STATE CORPORATION COMMISSION  
APR 18 1979

I certify that this is a true and correct copy of the above log to the best of my knowledge.

CONSERVATION DIVISION  
Wichita, Kansas

SAGE DRILLING CO., INC.

By T. M. McCaul, Jr.  
T. M. McCaul, Jr.



Subscribed and sworn to before me this 24th day of April, 1974.

Louise K. Whitted  
Louise K. Whitted, Notary Public

My commission expires:  
November 26, 1974.