


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Seward County, Sec. 29 Twp. 32S Rge. 31 E/WY
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines
C NW NE

Lease Owner Texas Energies, Inc.
Lease Name Monahan A Well No. 1
Office Address 306 Bk. of SW Amarillo, Texas 79109
Character of Well (Completed as Oil, Gas or Dry Hole)
Disposal Well



Locate well correctly on above
Section Plot

Date Well completed 19
Application for plugging filed 11-28 19 77
Application for plugging approved 11-30 19 77
Plugging commenced 12-5 19 77
Plugging completed 12-6 19 77
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Clarence Thomas
Producing formation Depth to top Bottom Total Depth of Well
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	1639	none
				5 1/2	5650	2010

Describe in detail the manner in which the well was plugged, indicating where the mud fluid
was placed and the method or methods used in introducing it into the hold. If cement or other
plugs were used, state the character of same and depth placed, from feet to
feet for each plug set.

Pump 10 sks. of cement & 2 sks. of hulls from 2900 to 3092
Pump 50 sks. of cement from 1639 to 1539
Put 10 sks. of cement from 140 to 0

RECEIVED
STATE CORPORATION COMMISSION

FEB 21 1978

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sargents Casing Pulling Service Box 506 Liberal, Kansas 67901

STATE OF KANSAS COUNTY OF Pratt, ss.
L.E. GOFFROY, Jr. (employee of owner) or (owner or operator)

of the above-described well, being first duly sworn on oath, says: That I have knowledge of
the facts, statements, and matters herein contained and the log of the above-described well
as filed and that the same are true and correct. So help me God.

(Signature) [Signature]
P.O. Box 176 Pratt, ks. 67124
(Address)



SUBSCRIBED AND SWORN TO before me this 20th day of February, 1978

[Signature]
Notary Public.

My commission expires Sept. 13, 1980

15-175-20063-0001

KANSAS GEOLOGICAL SURVEY
601 East 10th Ave
Wichita, Kansas

NOV 8 1969

Phillips Petroleum Company
Wichita, Kansas

Monahan "A"
1000 East 10th Ave
Wichita, Kansas 67202
Phillips Petroleum Company

Beckle Drilling Company
12 August 1969
3 September 1969

Drig. Contractor:
Date Completed:
Time Completed:

Operator

GLEN N. RUPE

DRY HOLE, SWDW, ETC.:

Well No.

#1

Lease Name

MONAHAN "A"

DRY HOLE

S 29 T 32 R 31 W

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.

TOP

BOTTOM

NAME

DEPTH

FORMATIONS TESTED

MORROW, DRY

5575

5579

MARMATON, GAS TOO SMALL
TO MEASURE

5026

5058

~~TOPERA~~

TORONTO, DRY

4320

4324

TOPERA, DRY

4145

4150

COUNCIL GROVE, GAS TOO SMALL
TO MEASURE

3068

3092

LOGS

VARIABLE INTENSITY CEMENT BOND LOG 5650' to 2500'

GAMMA RAY - COLLAR LOG 5650' to 2500'

SAMPLES

NO DRILLING SAMPLES TAKEN AS THIS WAS A WASH-DOWN OF AN OLD PHILLIPS WELL COMPLETED 9/18/69.

NO. 1
NO. 2
NO. 3

NOV 22 1969

RECEIVED
STATE CORPORATION COMMISSION

DEC 02 1977

CONSERVATION DIVISION
Wichita, Kansas

duf

ORIGINAL

NOV 8 1969

Phillips Petroleum Company
Borger, Texas

Drig. Contractor: Stickle Drilling Company
Date Commenced: 15 August 1969
Date Completed: 3 September 1969

Monahan "A" #1
1980' FEL & 660' FNL
Section 29-32S-31W
Seward County, Kansas

C Y W 115

DRILLER'S LOG

B 11


Depth figures indicate base of formation:

Sand, Clay, and Red Bed	590
Red Bed, Glor. Sand	1205
Red Bed and Gyp	1615
Gyp	1639
Anhydrite and Red Bed	1700
Red Bed	2240
Shale and Anhydrite	2537
Anhydrite and Shale	2652
Lime and Shale	2902
Lime	3820
Lime and Shale	4000
Lime	4120
Lime and Shale	4420
Lime	5632
Lime and Shale	5741
Lime	6150 RTD

RECEIVED
STATE CORPORATION COMMISSION
DEC 02 1977
CONSERVATION DIVISION
Wichita, Kansas

RECEIVED
STATE CORPORATION COMMISSION
SEP 19 1969
CONSERVATION DIVISION
Wichita, Kansas

I, Clifford M. Smith, hereby certify that to the best of my knowledge and belief, the above is a true and complete Driller's Log of Phillips Petroleum Company's Monahan "A" #1 in Seward County, Kansas.



Clifford M. Smith
Clifford M. Smith, Vice President

Wanda J. Steakley
Wanda J. Steakley, Notary Public
My Commission expires 16 January 1970.