

15-191-30189-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

OR
FORMATION PLUGGING RECORD

Strike out upper line when reporting plugging of formations.

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

Sumner County Sec. 20 Twp 30S Rge. 1 (E) (W) West
Location as "NE $\frac{1}{4}$ NW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines 150' NW of C SW/4 SW/4
Lease Owner HERNDON DRILLING CO.
Lease Name REUSSER Well No. 3
Office Address P.O. Box 489, Tulsa, Oklahoma 74101
Character of Well (completed as Oil, Gas or Dry Hole) OIL
Date well completed December 22 19 66
Application for plugging filed February 22 19 71
Application for plugging approved March 9 19 71
Plugging commenced June 23 19 71
Plugging completed June 26 19 71
Reason for abandonment of well or producing formation Uneconomical

NORTH

Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production January 19 71
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Ted Dewey
Producing formation Simpson Depth to top 3959' Bottom 3969' Total Depth of Well 3969' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Surface	Water			10 3/4"	389'	NONE
Simpson	Oil	3959'	3969'	4 1/2"	3964'	3089.43

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged hole back with chat from 3969 to 3959 - Mixed and dumped 3 sacks of cement on chat on bottom. Set bridge plug at 240 feet, bailed hole dry, put in 15 feet rock, 30 sacks cement, filled to 30 feet - Put in 10 feet of rock and 10 sacks of cement on top.

RECEIVED
STATE CORPORATION COMMISSION
JUL 2 - 1971
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to HERNDON DRILLING CO.
Address P.O. Box 489, Tulsa, Oklahoma 74101

STATE OF OKLAHOMA COUNTY OF TULSA, ss.
JAMES H. CHEW (employee of owner) or (owner or operator) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) James H. Chew
Box 489, Tulsa, Oklahoma 74101
(Address)

SUBSCRIBED AND SWORN to before me this 29th day of June, 1971

Dorthe L. Howard
Notary Public.

My commission expires October 21, 1973