


STATE OF KANSAS CORPORATION COMMISSION

Give All Information Completely Make Required Affidavit Mail or Deliver Report to: Conservation Division State Corporation Commission 212 North Market, Insurance Bldg. Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above Section Plat

MEADE County. Sec. 29 Twp. 32S. Rge. 30 (E) X (W) X Location as "NE/CNW/SW" or footage from lines 2310' FR. NORTH. 330' FR. EAST Lease Owner THE SHAMROCK OIL AND GAS CORPORATION Lease Name H. A. HOLMES "A" Well No. 1 Office Address BOX 631, AMARILLO, TEXAS Character of Well (completed as Oil, Gas or Dry Hole) DRY HOLE Date well completed APRIL 7 19 59 Application for plugging filed NOVEMBER 12 19 59 Application for plugging approved NOVEMBER 12 19 59 Plugging commenced NOVEMBER 12 19 59 Plugging completed NOVEMBER 18 19 59 Reason for abandonment of well or producing formation DRY

If a producing well is abandoned, date of last production 19 Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES.

Name of Conservation Agent who supervised plugging of this well FRANK BROADFOOT, ST. JOHNS, KANSAS Producing formation Depth to top Bottom Total Depth of Well 5695 Feet Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Table with 7 columns: FORMATION, CONTENT, FROM, TO, SIZE, PUT IN, PULLED OUT. Row 1: 9 5/8", 1650', - 0 -. Row 2: 5 1/2", 5691', 2500'.

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

PULLED 2500' OF 5 1/2" CASING. FILLED HOLE WITH MUD TO 450'. SET A 10' ROCK BRIDGE AND SPOTTED 20 SACKS OF CEMENT. FILLED HOLE WITH MUD UP TO 35' AND SET A 10' ROCK BRIDGE, AND SPOTTED 10 SACKS OF CEMENT. CEMENT CAME TO BASE OF CELLAR.

RECEIVED STATE CORPORATION COMMISSION

NOV 19 1959

CONSERVATION DIVISION Wichita, Kansas

(If additional description is necessary, use BACK of this sheet) Name of Plugging Contractor FORBES CASING PULLING COMPANY Address PRATT, KANSAS.

STATE OF TEXAS, COUNTY OF POTTER, ss. T. S. CLOPTON (employee of owner) or (owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) T. S. Clopton BOX 631, AMARILLO, TEXAS (Address)

SUBSCRIBED AND SWORN TO before me this 18TH day of NOVEMBER, 19 59

PAULINE POWELL Notary Public

My commission expires 6-1-61

H. A. HOLMES "A" # 1  
 SEC. 29, TWP. 32S. RGE. 30 W.  
 MEADE COUNTY, KANSAS

0'	-	250'	SAND & SHALE
250'	-	973'	SAND, SHALE & SHELLS
973'	-	1095'	RED BED & SHELLS
1095'	-	1215'	SAND
1215'	-	2345'	SHALE & SHELLS
2345'	-	2706'	SHALE & LIME
2706'	-	2777'	LIME
2777'	-	3145'	SHALE & LIME
3145'	-	3795'	CHALKY LIME & SHALE
3795'	-	3892'	LIME & SHALE
3892'	-	3933'	LIME
3933'	-	4518'	SHALE & LIME
4518'	-	4599'	LIME
4599'	-	4814'	LIME WITH SHALE STREAKS
4814'	-	4910'	LIME
4910'	-	5010'	LIME & SHALE
5010'	-	5560'	LIME
5560'	-	5563'	MARL
5563'	-	5569'	SAND
5569'	-	5579'	SHALE
5579'	-	5586'	SAND WITH SHALE STREAKS
5586'	-	5619'	LIME WITH SHALE STREAKS
5619'	-	5627'	SHALE
5627'	-	5634'	LIME
5634'	-	5695'	LIME WITH SHALE STREAKS

RECEIVED  
 STATE COMMISSION

NOV 1 1959

CONSERVA  
 Wichita