

15-119-10162-0000

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

MEADE County. Sec. 28 Twp. 32S Rge. 30 (X) (W)

Location as "NE/CNW/SW" or footage from lines 2310' FR. NORTH & EAST

Lease Owner THE SHAMROCK OIL & GAS CORPORATION

Lease Name H. A. HOLMES "B" Well No. 1

Office Address BOX 631, AMARILLO, TEXAS

Character of Well (completed as Oil, Gas or Dry Hole) DRY HOLE

Date well completed 8 - 19 1957

Application for plugging filed 8 - 19 1957

Application for plugging approved 8 - 19 1957

Plugging commenced 8 - 19 1957

Plugging completed 8 - 19 1957

Reason for abandonment of well or producing formation DRY HOLE

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well MERLE RIVES

Producing formation NONE Depth to top - Bottom - Total Depth of Well 5707 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
SAND	WATER	160'	455'	9 5/8"	1660.22'	- 0 -

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

FILLED HOLE WITH ROTARY MUD TO 530'. PUT IN 1/2 SACK OF HULLS AND PUSHED 9 5/8" OD HALLIBURTON TO 530'. SPOTTED 30 SACKS OF CEMENT FROM 530' TO 455'. LEFT WELL OPEN FROM 455' TO SURFACE TO BE USED AS A WATER WELL BY LANDOWNER.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor HALLIBURTON OIL WELL CEMENTING CO.  
Address GREAT BEND, KANSAS

STATE OF TEXAS, COUNTY OF POTTER, ss.  
DAN P. LONG (employee of owner) or (XXXXXX) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Dan P. Long  
Box 631, AMARILLO, TEXAS (Address)

SUBSCRIBED AND SWORN TO before me this 26TH day of AUGUST, 19 57

My commission expires 6-1-59  
Sandra Ritter, Notary Public, POTTER COUNTY, TEXAS STATE CORPORATION COMMISSION

PLUGGING  
FILE SEC 28 T 32 R30 W  
BOOK PAGE 39 LINE 28

AUG 27 1957  
CONSERVATION DIVISION  
Wichita, Kansas

*Shamrock Oil Gas*

HOLMES "B" #1  
SEC. 28 TWP 32S. RANGE 30 WEST  
MEADE COUNTY, OKLAHOMA

SWSWNE

0	-	165'	SURFACE, SAND, & CLAY
165'	-	980'	SAND, SHALE, SHELLS
980'	-	2400'	SHALE & ANHYDRITE
2400'	-	2685'	ANHYDRITE
2685'	-	2955'	DOLOMITE
2955'	-	3955'	LIME
3955'	-	4075'	LIME & SHALE
4075'	-	4930'	LIME
4930'	-	4990'	SHALE
4990'	-	5580'	SHALE & LIME
5580'	-	5612'	SAND & SHALE
5612'	-	5707'	SHALE & LIME

**PLUGGING**  
 FILE SEC. 28 T. 32 R. 30W  
 BOOK PAGE 39 LINE 28

RECEIVED  
 STATE CORPORATION COMMISSION  
 AUG 27 1957  
 COMPLETION DIVISION  
 STATE OF KANSAS