


15-119-10132-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION
Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

MEADE County. Sec. 27 Twp. 32 Rge. 30W. (NW) (W)



Locate well correctly on above Section Plat

Location as "NE/CNW/SW" or footage from lines NW NW NW
Lease Owner PETROLEUM, INC.
Lease Name HOLMES "D" Well No. 1
Office Address ROUTE 2, GREAT BEND, KANSAS
Character of Well (completed as Oil, Gas or Dry Hole) DRY HOLE
Date well completed September 15, 19 58
Application for plugging filed September 15, 19 58
Application for plugging approved September 16, 19 58
Plugging commenced September 15, 19 58
Plugging completed September 15, 19 58
Reason for abandonment of well or producing formation No Producing Zones
If a producing well is abandoned, date of last production None 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Merle Rives, Garden City, Kansas
Producing formation - - - - - Depth to top - - Bottom - - - Total Depth of Well 5805 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	1628'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Mud up with heavy mud to 100', pushed down wooden plug with drill pipe to 510' followed by 30 sacks cement.
Hole to be used as fresh water well by H.A. Holmes (Land Owner).

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Mid-Western Drillers Inc.
Address 1206 Mid-Continent Building, Tulsa, Oklahoma

STATE OF KANSAS, COUNTY OF BARTON, ss.
Don Searle (employee of owner) or (owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Don Searle
ROUTE 2, GREAT BEND, KANSAS (Address)

SUBSCRIBED AND SWORN TO before me this 30 th day of September, 19 58
My commission expires July 11, 1960
Notary Public.

OCT 1 1958
PLUGGING
FILE SEC 27 T. 32 R 30W
BOOK PAGE 29 LINE 27

DRILLERS LOG

Operator: Petroleum, Inc.
P. O. Box 309
Great Bend, Kansas

Elevation:
Date Commenced: Aug. 25, 1958

Contractor: Midwestern Drillers, Inc,
1206 Mid-Continent Bldg.
Tulsa, Oklahoma

Date Completed: Sept. 15, 1958

Lease Name: Holmes "D" #1

Total Depth: 5805' RB D & A

Lease Location: NW NW NW Sec. 27,
T32S, R 30W, Meade
County, Kansas

Casing Record: Surface - Set 1628' of 85/8" casing with 800
sacks pozmix with 2% CC.

Plugging - Hole filled with heavy mud. Set
Halliburton plug @ 510' and plugged with cement.

<u>Formation</u>	<u>Depth</u> <u>From Rotary Bushing</u>
Surface sand and clay	100
Sand and red bed	975
Red bed, sypsum and anhydrite	1,634 Ran 1628' of 85/8 casing
Red bed, shale and shells	2,120
Red bed and shale	2,320
Anhydrite and shale	2,416
Anhydrite and shale	2,605
Lime and shale	2,965
Lime, shale and dolomite	3,048
Lime and shale	3,492
Lime and shale	3,830
Lime, shale and chert	3,880
Lime and shale	4,172
Lime and shale	4,480
Lime	4,535
Lime and shale	4,760
Chalky lime	4,835
Lime	4,875
Lime and shale	4,970
Lime	5,080
Lime and shale	5,155
Lime	5,240
Lime and shale	5,404
Lime and shale	5,470
Lime with shale streaks	5,574 Ran DST #1 @ 5574'
Lime with shale streaks	5,632
Lime	5,705 Ran DST #2 @ 5705'
Lime	5,805 Ran Electric Log @ 5805'
	TD Plugged. D & A

I hereby certify that the above is true and correct
copy of Drillers Log on the Holmes "D" #1 of Petroleum, Inc.

MIDWESTERN DRILLERS, INC.

BY J. H. Morrison

Subscribed and sworn to before me this 20th day of September, 1958
My commission expires

F. W. Warrant
Notary Public

OGC 1958

PLUGGING
FILE SEC 27 T. 32 R. 30W
BOOK PAGE 129 LINE 27