

STATE OF KANSAS
STATE CORPORATION COMMISSION
Finney State Office Building
130 South Market, Rm 2078
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-119-20969 - 0000

LEASE NAME PAGE "A"

WELL NUMBER 1

3300 Ft. from S Section Line

660 Ft. from E Section Line

SEC. 25 TWP. 32 RGE. 30 (X) or (W)

COUNTY MEADE

Date Well Completed 12-4-96

Plugging Commenced 1-27-97

Plugging Completed 1-30-97

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days

LEASE OPERATOR ANADARKO PETROLEUM CORPORATION

ADDRESS P.O. BOX 351, LIBERAL, KS 67901-0351

PHONE # (316) 624-6253 OPERATORS LICENSE NO. 4549

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 1-21-97 (date)

by GARY WINTERS (KCC District Agent's Name).

Is AC0-1 filed? YES (ATTACHED) If not, is well log attached? ATTACHED

Producing Formation NONE Depth to Top _____ Bottom _____ T.D. 6150'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8-5/8	1640	NONE
				5-1/2	5700	3101'

Describe in detail, the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each set.
MIRU PLUGGERS, PMPD 2 SX HULLS & 30 SX CMT FROM 5588-5388', SHOT OFF 5-1/2" CSG @ 3101', TOH W/5-1/2" CSG TO 3100', & SPOT 30 SX FROM 3000-3100', TOH TO 1660' & SPOT 50 SX PLUG FROM 1510-1660', TOH TO 650' & SPOT 40 SX FROM 550-650', TOH TO 40' & SPOT 10 SX PLUG FROM 40' TO 0'. (HEAVY DRILLING MUD PUMPED BETWEEN EACH PLUG). CUT OFF & CAP 8-5/8 CSG 4' BELOW GL. PERMANENTLY INSCRIBE WELL NAME, LEGAL LOCATION AND DATE PLUGGED ON CAP.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor: SARGENT & HORTON PLUGING, INC. License No. 31151
Address P O BOX 49BA, TYRONE, OKLAHOMA 73951-9731

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: ANADARKO PETROLEUM CORPORATION

STATE OF KANSAS COUNTY OF SEWARD, ss.

DAVID W. KAPPLE (Employee of Operator) or (xxxxxxx) of above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) David W. Kapple

(Address) DAVID W. KAPPLE
P.O. BOX 351, LIBERAL, KS 67901-0351

SUBSCRIBED AND SWORN TO before me this 1st day of February, 19 97

L. MARC HARVEY
Notary Public - State of Kansas
My Appt. Expires 6-18-99

Notary Public

RECORDED
STATE CORPORATION COMMISSION

FEB 11 1997

CONSERVATION DIVISION
Wichita, Kansas

Form CP-4
Revised 05-88