


STATE OF KANSAS
CORPORATION COMMISSION

All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

Seward County, Sec. 19 Twp. 32 Rge. 31W (E) (W)
Location as "NE/CNW/SW" or footage from lines NW SE NW
Lease Owner J. M. Huber Corporation
Lease Name Barnum Well No. 1;
Office Address _____
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed Jan. 6 1962
Application for plugging filed Jan. 6 - verbally 1962
Application for plugging approved Jan. 6 - verbally 1962
Plugging commenced Jan. 6 1962
Plugging completed Jan. 6 1962
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well W. L. LaKamp
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 5905 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	2379	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Ran 25 stds. in hole with 8 5/8 plug to 2371, spot 35 sx cement through drill pipe. Fill hole with mud to 40', 8 5/8" plug with 15 sx cement, 5 sx in rat hole.

RECEIVED
STATE CORPORATION COMMISSION

JAN 10 1962

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor _____
Address _____

STATE OF KANSAS, COUNTY OF RUSSELL
Donald L. Roberts of Roberts Drill Co., drilling contractor
(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) By Donald L. Roberts
Managing Partner
Russell, Ks.
(Address)

SUBSCRIBED AND SWORN TO before me this 10th day of January, 19 62

Charles L. [Signature]
Notary Public.

My commission expires 6/17/62



J. M. HUBER CORPORATION
BARNUM #1

NW SE NW Sec. 19-32-31W
Seward County, Kansas

R.T.D. 5905'

CONTRACTOR: Roberts Drilling Co.

Commenced: 12/9/61
Completed: 1/6/62

Set @ 5/8" @ 2379' w/1180 sx cmt.

Surface Soil & Shale	40'
Sandy Shale	75
Surface Clay	133
Sand & Clay	560
Red Bed	607
Red Bed & Sand	996
Red Bed, Gypson, Anhyd.	1106
Red Bed & Shale	1255
Shale & Sand	1295
Red Bed & Shale	1544
Red Bed & Anhyd. Streaks	1555
Sandy Red Bed	1637
Anhydrite	1665
Anhyd. Streaks & Sand	1675
Lime & Shale	3185
Lime, Shale & Chalk	3415
Lime & Chalk Streaks	3525
Lime & Chalk	3603
Chalky Lime	3873
Lime & Chert	3919
Hard Lime	3985
Lime	4034
Lime & Shale	4368
Lime	4502
Lime & Shale	4605
Lime	4660
Lime & Chert	4750
Lime	4870
Lime & Shale	4920
Lime	5441
Lime & Shale	5494
Lime	5575
Lime & Shale	5625
Lime	5661
Lime & Shale	5840
Lime	5890
Lime & Shale	5905

RECEIVED
STATE CORPORATION
JAN 12 1962
CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS)
RUSSELL COUNTY) SS.

I hereby certify that the above information is correct to the best of my knowledge.

ROBERTS DRILLING CO.

By Donald L. Roberts
Donald L. Roberts

Subscribed and sworn to before me this 10th day of January, 1962.

Charles Hummel
Notary Public

My Commission Expires 6/17/62