

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-175-21130-0000

LEASE NAME Beck

TYPE OR PRINT

NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

WELL NUMBER 1-16

4380 Ft. from S Section Line

3380 Ft. from E Section Line

SEC. 16 TWP. 32 RGE. 31 (E) or (W)

COUNTY Seward

Date Well Completed 4/2/90

Plugging Commenced 6/25/90

Plugging Completed 6/27/90

LEASE OPERATOR Parker & Parsley Petroleum Company

ADDRESS 205 NW 63rd, Suite 220 Oklahoma City, OK 73116

PHONE# (405) 848-2204 OPERATORS LICENSE NO. 03908

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved filed on 6/11/90 (date)

plugging witnessed by KCC Field Inspector (KCC District Agent's Name).

Is ACO-1 filed? yes If not, is well log attached? \_\_\_\_\_

Producing Formation None Depth to Top NA Bottom NA T.D. 5700

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Lansing	water	4372	4884	12.75	603	3
Marmaton	water	5050	5116	8.625	1729	3
Morrow	water	5116	5605	4.5	5700	2500

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.  
Tested Morrow @ 5550-64. Set retainer @ 5130. 200 sx annular squeeze. Tested Marmaton @ 5056-66. Pump 10 sx class H to 4956'-5056'. Displace w/ mud. Shot & pulled 4 1/2" csg @ 2500. Pump 50 sx class H to 1799-1679 via rbg. Displace w/ mud. Pump 30 sx @ 700'-612'. Displace w/ mud. Pump 15 sx @ 40'-surf. Pump 17 sx between 12-3/4" and 8-5/8" via 1" pipe. Cut off csg. Weld on plate.  
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Parker & Parsley Petroleum Co License No. 03908

Address 205 NW 63rd, Suite #220 Oklahoma City, OK 73116

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: same

STATE OF Oklahoma COUNTY OF Canadian, ss.

Mike Stafford Mike Stafford (Employee of Operator or Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Mike Stafford

(Address) 205 N.W. 63rd, Suite 220  
Oklahoma City, Oklahoma 73116

SUBSCRIBED AND SWORN TO before me this 20th day of July, 19 90

My Commission Expires: August 28, 1990  
Notary Public