

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Seward County, Sec. 14 Twp. 32 Rge. 31 ~~W~~
Location as "NE/CNW $\frac{1}{2}$ SW $\frac{1}{2}$ " or footage from lines
C-NW-NW-NW

Lease Owner Tucker Production
Lease Name Reiss #1 Well No. _____
Office Address 2546 W. Main, Littleton Colo. 80120

Character of Well (Completed as Oil, Gas or Dry Hole)
Gas or Oil - Dry hole


Date Well completed, 11/15/80 19
Application for plugging filed 9-18-80 19
Application for plugging approved 9-19-80 19
Plugging commenced 9-19-80 19
Plugging completed 9-20-80 19

Reason for abandonment of well or producing formation
Non Commercial Value

If a producing well is abandoned, date of last production
None 19

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Mr. Thomas
Producing formation, Morrow Depth to top 4646 Bottom 5827 Total Depth of Well 5956
Show depth and thickness of all water, oil and gas formations.



Locate well correctly on above
Section Plot


OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface				8 5/8"	1699'	0'
Production				4 1/2"	5956'	2854'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Squeezed bottom perms w/125 sks. cement - Top of Cement 4000'
Pumped 35 sks cement 1700' to 1600'
Displaced to 750'
Pumped 25 sks cement 750' to 675'
Displaced to 40'
Put bridge & 10 sks cement 40' to 0'
Cut off 8 5/5" - 42" below ground level & weld plate



(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Midwest Casing Pulling, Kansas permit # 766

STATE OF KANSAS COUNTY OF HASKELL, ss.
I, Edgar J. Eves (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Edgar J. Eves
Box 7, Sublette, Ks. 67877
(Address)

SUBSCRIBED AND SWORN TO before me this 22 day of Nov., 19 80

Sondra L. Eves
Notary Public.

My commission expires 12-6-80



Rh18

WELL LOG

COMPANY Macey & Mershon Oil, Inc.

SEC. 14-32S-31W

FARM Reiss

NO. 1

LOC. 330' FNL & 330' FWL

TOTAL DEPTH 6000

COUNTY Seward, Kansas

COMM. 12/30/79

COMP. 1/13/80

CONTRACTOR Zenith Drilling Corporation

CASING
1699' of 8 5/8", 24# casing, cemented with 1000 sacks
cement

ELEVATION

PRODUCTION

FIGURES INDICATE BOTTOM OF FORMATIONS

103	Sand
1480	Sand & Red Bed
1700	Red Bed & Anhydrite
1760	Red Bed & Shells
2290	Shells
2660	Sand & Shale
3995	Lime & Shale
4135	Lime
6000	Lime & Shale

State of KANSAS }
 County of SEDGWICK } ss

I, Emmet E. Hall of Zenith Drilling Corporation
 upon oath state the above and foregoing is a true and correct copy of the log of the Reiss #1 well.

Subscribed and sworn to before me this 16th day of January, 1980

My Commission Expires: Dec. 15, 1980

Sharon R. Allen
 Sharon R. Allen NOTARY PUBLIC